

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, May 30, 2025**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION: GMRC BRIDGE NO. 132 OVER BLACK RIVER AT MILE POST 24.31

TYPE OF CONSTRUCTION: REHABILITATION OF EXISTING TWO SPAN SKEWED STEEL THROUGH PLATE GIRDER STRUCTURE REHABILITATION OF PORTIONS OF THE EXISTING ABUTMENT STEMS, WINGWALLS, BACKWALLS AND BEARINGS; REPLACEMENT OF PIER AND APPROACH TRACK WORK

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **October 23, 2026**.

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER'S ESTIMATE: For this proposal the Engineer's Estimate is **Category E**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
<https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting>

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30pm on Wednesday, May 21, 2025.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: <https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf>, and must be submitted/uploaded through the iCXWeb website at: <https://vtrans.exevision.com/icx/Index.aspx>

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
<https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications>

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at: <https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding>

RAILROAD PROTECTIVE LIABILITY INSURANCE: Prospective Bidders/Contractors are hereby notified that Railroad

Protective Liability Insurance is required for this Contract in accordance with Subsection 103.04(d) of the 2024 Standard Specifications for Construction. The Railroad Protective Liability Form is not included in the Proposal. The form will be provided by the successful Bidder's insurance company.

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
199.9999	LIQUIDATED DAMAGES, TRAIN DELAY (N.A.B.I.)	1.000	DL
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	1.000	LS
203.1500	COMMON EXCAVATION	150.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000	CY
204.2500	STRUCTURE EXCAVATION	25.000	CY
208.3000	COFFERDAM EXCAVATION, EARTH	85.000	CY
208.3500	COFFERDAM EXCAVATION, ROCK	15.000	CY
208.4000	COFFERDAM	1.000	LS
240.0300	TEMPORARY RAILROAD ACCESS	1.000	LS
301.2600	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	80.000	CY
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	20.000	CY
501.3800	PERFORMANCE-BASED CONCRETE, CLASS PCS	65.000	CY
501.3900001	PERFORMANCE-BASED CONCRETE, CLASS HSSCC	100.000	CY
502.1000	SHORING SUPERSTRUCTURE	1.000	LS
504.1000	FURNISHING EQUIPMENT FOR DRIVING PILING	1.000	LS
505.2000	STEEL PILING, HP 14 x 117	1,060.000	LF
505.4500	DYNAMIC PILE LOADING TEST	2.000	EACH
506.5000	STRUCTURAL STEEL, ROLLED BEAM	151,000.00	LB
		0	
506.6000	STRUCTURAL STEEL	29,000.000	LB
506.8500	RIVET REPLACEMENT	40.000	EACH
507.1100	REINFORCING STEEL, LEVEL I (EPOXY COATED)	12,000.000	LB
507.1200	REINFORCING STEEL, LEVEL II (GALVANIZED)	64,000.000	LB
507.1600	DRILLING AND GROUTING DOWELS	35.000	LF
511.1002	REMOVAL, CONTAINMENT, AND DISPOSAL OF LEAD PAINT, TYPE II	1.000	LS
514.1000	WATER REPELLENT, SILANE	25.000	GAL
529.2000	PARTIAL REMOVAL OF STRUCTURE	1.000	EACH
531.1800	BEARING DEVICE ASSEMBLY, ELASTOMERIC PAD W/EXT. LOAD PLATES	4.000	EACH
542.1000	HIGH PERFORMANCE CONCRETE, RAPID SET	10.000	CY
602.3500	REBUILT STONE MASONRY	20.000	CY
602.4000	REPAIRING STONE MASONRY	50.000	SY
613.1004	STONE FILL, TYPE IV	25.000	CY
614.2000	IN-WATER SEDIMENT ISOLATION MEASURES	1.000	LS
630.1000	UNIFORMED TRAFFIC OFFICERS	80.000	HR
630.1500	FLAGGERS	800.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1600	TESTING EQUIPMENT, CONCRETE	1.000	LS
631.1900	TESTING EQUIPMENT, GROUT	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	3,000.000	DL
632.1000	RAILROAD FLAGGERS (N.A.B.I.)	72,000.000	DL
633.1000	CPM SCHEDULE	6.000	EACH
635.1100	MOBILIZATION/DEMOBILIZATION	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE	1.000	LS

649.2100	GEOTEXTILE UNDER RAILROAD BALLAST	60.000	SY
651.1500	TURF ESTABLISHMENT, GENERAL SEED	2,400.000	SY
651.3500	TOPSOIL	70.000	CY
653.0100	EPSC PLAN	1.000	LS
653.0200	MONITORING EPSC PLAN	80.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	10,000.000	DL
653.1000	HAY MULCH	1.000	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	610.000	SY
653.3500	STABILIZED CONSTRUCTION ENTRANCE	40.000	CY
653.4500	FILTER BAG	4.000	EACH
653.4702	SILT FENCE, TYPE II	1,250.000	LF
653.5000	BARRIER FENCE	4,800.000	LF
653.6000	EROSION LOG	100.000	LF
662.0010	RAILROAD BALLAST	80.000	TON
662.0110	REMOVE AND REPLACE BRIDGE TIES	158.000	EACH
662.0250	REMOVE AND RESET JOINTED RAILROAD TRACK	290.000	LF
662.0410	RAISE, ALIGN, AND SURFACE TRACK	900.000	LF
662.0450	GAGING TRACK	290.000	LF
OPTION - ABUTMENT 1 CONCRETE OPTION - ABUT 1 PRECAST CONCRETE			
540.1000	PRECAST CONCRETE STRUCTURE (ABUTMENT 1)	1.000	LS
OPTION - ABUTMENT 1 CONCRETE OPTION - ABUT 1 CONTRACTOR FABRICATED CONCRETE			
543.1000	CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE (ABUTMENT 1)	1.000	LS
OPTION - ABUTMENT 2 CONCRETE OPTION - ABUT 2 PRECAST CONCRETE			
540.1000	PRECAST CONCRETE STRUCTURE (ABUTMENT 2)	1.000	LS
OPTION - ABUTMENT 2 CONCRETE OPTION - ABUT 2 CONTRACTOR FABRICATED CONCRETE			
543.1000	CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE (ABUTMENT 2)	1.000	LS

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.