

### INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, June 13, 2025**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

**LOCATION:** LOCATED ON TH 1 (SOUTH ST) OVER THE POULTNEY RIVER IN THE TOWN OF POULTNEY, APPROXIMATELY 0.17 MILES SOUTH OF THE INTERSECTION WITH TH 7 (BENTLEY AVE).

**TYPE OF CONSTRUCTION:** REHABILITATION OF THE STEEL TRUSS, REMOVAL AND REPLACEMENT OF THE ABUTMENTS, AND RELATED APPROACH ROADWAY AND CHANNEL WORK.

**CONTRACT COMPLETION DATE:** This Contract shall be completed on or before **August 27, 2027**.

**BID BOND:** Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

**ENGINEER'S ESTIMATE:** For this proposal the Engineer's Estimate is **Category F**.

**PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY:** On the VTrans website at:  
<https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting>

**QUESTIONS:** During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: [AOT.ConstructionContractingInquiry@vermont.gov](mailto:AOT.ConstructionContractingInquiry@vermont.gov). All inquiries must be received by 4:30pm on Wednesday, June 04, 2025.

**PREQUALIFICATION OF CONTRACTORS:** All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: <https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf>, and must be submitted/uploaded through the iCXWeb website at: <https://vtrans.exevision.com/icx/Index.aspx>

**STANDARD SPECIFICATIONS:** The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.  
<https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications>

**NON-COLLUSION AFFIDAVIT:** All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

**NONDISCRIMINATION IN AGENCY CONTRACTS:** VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

**MANDATORY ELECTRONIC BIDDING:** Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at:  
<https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding>

## TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

## ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	1.000	LS
203.1500	COMMON EXCAVATION	1,900.000	CY
203.2700	UNCLASSIFIED CHANNEL EXCAVATION	500.000	CY
203.3000	EARTH BORROW	200.000	CY
203.3100	SAND BORROW	440.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000	CY
204.2500	STRUCTURE EXCAVATION	770.000	CY
204.3000	GRANULAR BACKFILL FOR STRUCTURES	400.000	CY
210.1000	COARSE-MILLING, BITUMINOUS PAVEMENT	280.000	SY
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	1,200.000	CY
401.1000	AGGREGATE SURFACE COURSE	20.000	CY
402.1300	AGGREGATE SHOULDERS, RAP	50.000	TON
404.1100	TACK COAT, EMULSIFIED ASPHALT	30.000	CWT
406.0230	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III	360.000	TON
406.0430	BITUMINOUS CONCRETE PAVEMENT, TYPE IVS, QA TIER III	270.000	TON
406.3400	BITUMINOUS CONCRETE PAVEMENT, NON-PAVER PLACED, TYPE IVS	200.000	SY
406.9100	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	1.000	DL
406.9200	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	1.000	DL
501.3700	PERFORMANCE-BASED CONCRETE, CLASS PCD	30.000	CY
501.3800	PERFORMANCE-BASED CONCRETE, CLASS PCS	360.000	CY
506.5000	STRUCTURAL STEEL, ROLLED BEAM	68,700.000	LB
506.5700	STRUCTURAL STEEL, TRUSS	44,625.000	LB
506.6000	STRUCTURAL STEEL	900.000	LB
507.1100	REINFORCING STEEL, LEVEL I	15,330.000	LB
507.1100	REINFORCING STEEL, LEVEL I (EPOXY COATED)	9,740.000	LB
507.1200	REINFORCING STEEL, LEVEL II	8,010.000	LB
508.1500	SHEAR CONNECTORS	1.000	LS
509.1500	CONCRETE BRIDGE DECK SURFACE PREPARATION	2,650.000	SF
511.1001	REMOVAL, CONTAINMENT, AND DISPOSAL OF LEAD PAINT, TYPE I	1.000	LS
513.1030	FIELD PAINTING STEEL, THREE COAT SYSTEM	1.000	LS
514.1000	WATER REPELLENT, SILANE	50.000	GAL
516.100001	BRIDGE EXPANSION JOINT, PRE-COMPRESSED	31.000	LF
524.1100	JOINT SEALER, HOT POURED	21.000	LF
525.3130	BRIDGE RAILING, GALVANIZED 3 RAIL BOX BEAM	270.000	LF
525.6100	BRIDGE RAILING, METAL TRUSS BRIDGE	132.000	LF
528.1000	ONE LANE TEMPORARY BRIDGE (4800 SF - EST)	1.000	LS
529.2000	PARTIAL REMOVAL OF STRUCTURE	1.000	EACH
531.1800	BEARING DEVICE ASSEMBLY, ELASTOMERIC PAD W/EXT. LOAD PLATES	4.000	EACH
547.1000	MICROPILE, CASED	1,300.000	LF
547.1500	MICROPILE, UNCASD	690.000	LF
547.2000	MICROPILE OBSTRUCTION DRILLING AND REMOVAL	100.000	LF
547.2500	FURNISHING EQUIPMENT FOR INSTALLING MICROPILES	1.000	LS
547.3000	MICROPILE VERIFICATION LOAD TEST	1.000	EACH
547.3500	MICROPILE PROOF LOAD TEST	2.000	EACH
550.1000	METAL GRID REINFORCED CONCRETE BRIDGE DECK	2,800.000	SF
604.4200	CHANGING ELEVATION OF SEWER MANHOLES	1.000	EACH

613.0603	E-STONE FILL, TYPE III	290.000	CY
613.1003	STONE FILL, TYPE III	180.000	CY
614.2000	IN-WATER SEDIMENT ISOLATION MEASURES	1.000	LS
616.2702	CAST-IN-PLACE CONCRETE CURB, TYPE B	460.000	LF
616.4100	REMOVAL OF EXISTING CURB	280.000	LF
618.1005	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	250.000	SY
618.3000	DETECTABLE WARNING SURFACE	10.000	SF
620.1006	CHAIN-LINK FENCE, 6 FOOT	170.000	LF
620.1008	CHAIN-LINK FENCE, 8 FOOT	70.000	LF
620.8200	SQUARE STEEL FENCE	100.000	LF
620.8200001	VEHICULAR GATE	1.000	EACH
621.0100	REMOVAL OF GUARDRAIL	100.000	LF
621.2300	BOX BEAM GUARDRAIL	40.000	LF
621.2400	TEMPORARY TRAFFIC BARRIER	700.000	LF
621.4030	MTS, BOX BEAM, TANGENT, TL-3	4.000	EACH
621.7030	ENERGY ABSORPTION ATTENUATOR, TEMPORARY, TL-3	3.000	EACH
621.8130	GUARDRAIL APPROACH SECTION, 3 RAIL BOX BEAM	4.000	EACH
629.3600	RELOCATE HYDRANT	1.000	EACH
630.1000	UNIFORMED TRAFFIC OFFICERS	150.000	HR
630.1500	FLAGGERS	2,400.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1600	TESTING EQUIPMENT, CONCRETE	1.000	LS
631.1700	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.1800	TESTING EQUIPMENT, PROTECTIVE COATINGS	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	6,000.000	DL
633.1000	CPM SCHEDULE	24.000	EACH
634.1000	EMPLOYEE TRAINEESHIP	1,560.000	HR
635.1100	MOBILIZATION/DEMOBILIZATION	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE	1.000	LS
641.2100	TEMPORARY TRAFFIC CONTROL SIGNAL SYSTEM, FIXED	1.000	EACH
641.2200001	DRIVEWAY ASSISTANCE DEVICE	5.000	EACH
646.4040	DURABLE 4 INCH WHITE LINE, POLYUREA	1,500.000	LF
646.4140	DURABLE 4 INCH YELLOW LINE, POLYUREA	1,500.000	LF
646.7600	LINE STRIPING TARGETS	300.000	EACH
649.3100	GEOTEXTILE UNDER STONE FILL	420.000	SY
651.1500	TURF ESTABLISHMENT, GENERAL SEED	2,090.000	SY
651.1600	TURF ESTABLISHMENT, SPECIALTY SEED	1,520.000	SY
651.3500	TOPSOIL	380.000	CY
651.4012	GRUBBING MATERIAL, 12 INCH	190.000	SY
653.0100	EPSC PLAN	1.000	LS
653.0200	MONITORING EPSC PLAN	290.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	5,000.000	DL
653.1000	HAY MULCH	1.000	TON
653.1200	STRAW MULCH	1.000	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	210.000	SY
653.3500	STABILIZED CONSTRUCTION ENTRANCE	35.000	CY
653.4001	INLET PROTECTION DEVICE, TYPE I	2.000	EACH
653.4500	FILTER BAG	2.000	EACH
653.4702	SILT FENCE, TYPE II	310.000	LF
653.5000	BARRIER FENCE	490.000	LF
653.5500	PROJECT DEMARCATION FENCE	560.000	LF
656.2003	EVERGREEN TREES, LARGE	7.000	EACH
656.3002	DECIDUOUS TREES, MEDIUM	47.000	EACH
656.3003	DECIDUOUS TREES, LARGE	2.000	EACH
656.3500	DECIDUOUS SHRUBS	167.000	EACH
656.6500	LANDSCAPE WATERING	70.000	MGAL
656.8000	LANDSCAPE BACKFILL, TRUCK MEASUREMENT	50.000	CY

656.8500	TREE PROTECTION	1.000	LS
675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	12.000	SF
675.3410	SQUARE TUBE SIGN POST AND ANCHOR	155.000	LF
675.5000	SIGN REMOVAL, FLAT SHEET ALUMINUM	8.000	EACH
675.6000	RESETTING SIGNS	7.000	EACH
675.6000001	REMOVE AND RESET PRIVATE SIGN ASSEMBLY, NON-LIGHTED	1.000	EACH
690.0300	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	1.000	DL

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.