

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, July 11, 2025**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

ADDITIONAL BID INFORMATION:

LOCATION: On VT Route 114 in the Town of Norton approximately 1.8 miles south of the international United States/Canadian border.

TYPE OF CONSTRUCTION: Removal of existing culvert, and replacement with a new open bottom buried structure.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **October 16, 2026**.

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER's ESTIMATE: For this proposal the Engineer's Estimate is **Category D**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
<https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting>

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30pm on Wednesday, July 02, 2025.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: <https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf>, and must be submitted/uploaded through the iCXWeb website at: <https://vtrans.exevision.com/icx/Index.aspx>

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
<https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications>

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at:
<https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding>

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
199.8121	LIQUIDATED DAMAGES, INTERIM COMPLETION DATE (N.A.B.I.)	1.000	DL
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	1.000	LS
203.1500	COMMON EXCAVATION	1,060.000	CY
203.1600	SOLID ROCK EXCAVATION	10.000	CY
203.2700	UNCLASSIFIED CHANNEL EXCAVATION	480.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000	CY
204.2500	STRUCTURE EXCAVATION	1,430.000	CY
204.3000	GRANULAR BACKFILL FOR STRUCTURES	770.000	CY
210.1000	COARSE-MILLING, BITUMINOUS PAVEMENT	320.000	SY
240.0100002	TEMPORARY ROADWAY WIDENING	1.000	LS
250.0100	CONSTRUCTION VIBRATION AND CRACK MONITORING	1.000	LS
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	650.000	CY
401.1000	AGGREGATE SURFACE COURSE	70.000	CY
404.1100	TACK COAT, EMULSIFIED ASPHALT	15.000	CWT
406.0220	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER II	263.000	TON
406.0330	BITUMINOUS CONCRETE PAVEMENT, TYPE IIIS, QA TIER III	353.000	TON
406.9100	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	1.000	DL
406.9200	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	1.000	DL
507.1100	REINFORCING STEEL, LEVEL I	1,485.000	LB
507.1600	DRILLING AND GROUTING DOWELS	278.000	LF
514.1000	WATER REPELLENT, SILANE	15.000	GAL
529.1500	REMOVAL OF STRUCTURE (10 FT DIA X 80 FT LONG)	1.000	EACH
540.1000	PRECAST CONCRETE STRUCTURE (22 FT X 12 FT X 54 FT RIGID FRAME WITH WINGWALLS)	1.000	LS
541.2300	CONCRETE, CLASS C	274.000	CY
608.2501	ALL-PURPOSE EXCAVATOR RENTAL, TYPE I	10.000	HR
609.1000	DUST CONTROL WITH WATER	81.000	MGAL
613.0602	E-STONE FILL, TYPE II	320.000	CY
613.1001	STONE FILL, TYPE I	80.000	CY
614.1000	TEMPORARY RELOCATION OF STREAM	1.000	EACH
621.0100	REMOVAL OF GUARDRAIL	921.000	LF
621.1060	STEEL BEAM GUARDRAIL	613.000	LF
621.3120	MTS, MGS, FLARED, TL-2	3.000	EACH
630.1000	UNIFORMED TRAFFIC OFFICERS	100.000	HR
630.1500	FLAGGERS	600.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1600	TESTING EQUIPMENT, CONCRETE	1.000	LS
631.1700	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.1900	TESTING EQUIPMENT, GROUT	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	3,000.000	DL
633.1000	CPM SCHEDULE	6.000	EACH
634.1000	EMPLOYEE TRAINEESHIP	520.000	HR
635.1100	MOBILIZATION/DEMobilIZATION	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE	1.000	LS
641.1500	PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH
641.2200	TEMPORARY TRAFFIC CONTROL SIGNAL SYSTEM, PORTABLE	1.000	EACH
646.2010	4 INCH WHITE LINE, WATERBORNE PAINT	1,200.000	LF

646.2111	4 INCH YELLOW LINE, WATERBORNE PAINT	1,200.000	LF
649.1100	GEOTEXTILE FOR ROADBED SEPARATOR	2,070.000	SY
649.3100	GEOTEXTILE UNDER STONE FILL	80.000	SY
651.1500	TURF ESTABLISHMENT, GENERAL SEED	185.000	SY
651.1600	TURF ESTABLISHMENT, SPECIALTY SEED	185.000	SY
651.1700	TURF ESTABLISHMENT, TEMPORARY SEED	185.000	SY
651.3500	TOPSOIL	25.000	CY
651.4000	GRUBBING MATERIAL	140.000	SY
653.0100	EPSC PLAN	1.000	LS
653.0200	MONITORING EPSC PLAN	100.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	3,000.000	DL
653.1000	HAY MULCH	0.250	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	190.000	SY
653.2501	CHECK DAM, TYPE I	2.000	CY
653.3500	STABILIZED CONSTRUCTION ENTRANCE	31.000	CY
653.4701	SILT FENCE, TYPE I	1,140.000	LF
653.5000	BARRIER FENCE	455.000	LF
653.5500	PROJECT DEMARCATION FENCE	682.000	LF
656.3500	DECIDUOUS SHRUBS	45.000	EACH
656.8500	TREE PROTECTION	1.000	LS
675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	0.800	SF
675.3410	SQUARE TUBE SIGN POST AND ANCHOR	16.000	LF
675.5000	SIGN REMOVAL, FLAT SHEET ALUMINUM	2.000	EACH
676.1000	DELINEATOR WITH STEEL POST	3.000	EACH
690.0300	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	1.000	DL

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.