

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, November 14, 2025**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION: BEGINNING IN THE TOWN OF NORTON ON VT ROUTE 114 AT STATION 300+50.00 (MM 5.691) AND EXTENDING NORTHERLY 75.00 FT (0.014 MILES) TO STATION 301+25.00 (MM 5.705)

TYPE OF CONSTRUCTION: WORK TO BE PERFORMED UNDER THIS PROJECT INCLUDES REMOVAL OF A FAILING CONCRETE CULVERT, INSTALLATION OF A NEW PRECAST CONCRETE BOX CULVERT, HEADWALLS, WINGWALLS, CHANNEL IMPROVEMENTS, AND OTHER HIGHWAY-RELATED ITEMS.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **October 15, 2026**.

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER'S ESTIMATE: For this proposal the Engineer's Estimate is **Category D**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
<https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting>

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30pm on Wednesday, November 05, 2025.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: <https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf>, and must be submitted/uploaded through the iCXWeb website at: <https://vtrans.exevision.com/icx/Index.aspx>

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
<https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications>

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at:
<https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding>

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|-------------|--|-----------|-------|
| 201.1000 | CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS | 1.000 | LS |
| 203.1500 | COMMON EXCAVATION | 600.000 | CY |
| 203.2700 | UNCLASSIFIED CHANNEL EXCAVATION | 425.000 | CY |
| 204.2000 | TRENCH EXCAVATION OF EARTH | 5.000 | CY |
| 204.2200 | TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.) | 1.000 | CY |
| 204.2500 | STRUCTURE EXCAVATION | 400.000 | CY |
| 204.3000 | GRANULAR BACKFILL FOR STRUCTURES | 160.000 | CY |
| 210.1000 | COARSE-MILLING, BITUMINOUS PAVEMENT | 950.000 | SY |
| 240.0100003 | TEMPORARY TRAFFIC DIVERSION | 1.000 | LS |
| 301.3500 | SUBBASE OF DENSE GRADED CRUSHED STONE | 550.000 | CY |
| 401.1000 | AGGREGATE SURFACE COURSE | 35.000 | CY |
| 402.1300 | AGGREGATE SHOULDERS, RAP | 10.000 | TON |
| 404.1100 | TACK COAT, EMULSIFIED ASPHALT | 12.000 | CWT |
| 406.0230 | BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III | 135.000 | TON |
| 406.0330 | BITUMINOUS CONCRETE PAVEMENT, TYPE IIIS, QA TIER III | 145.000 | TON |
| 406.3400 | BITUMINOUS CONCRETE PAVEMENT, NON-PAVER PLACED, TYPE IVS | 85.000 | SY |
| 406.9100 | PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.) | 1.000 | DL |
| 406.9200 | PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.) | 1.000 | DL |
| 540.1000 | PRECAST CONCRETE STRUCTURE (12 FT-0 IN X 6 FT-0 IN X 52 FT-0 IN BOX) | 1.000 | LS |
| 613.0602 | E-STONE FILL, TYPE II | 320.000 | CY |
| 614.1000 | TEMPORARY RELOCATION OF STREAM | 1.000 | EACH |
| 621.0100 | REMOVAL OF GUARDRAIL | 100.000 | LF |
| 630.1000 | UNIFORMED TRAFFIC OFFICERS | 80.000 | HR |
| 630.1500 | FLAGGERS | 600.000 | HR |
| 631.1000 | FIELD OFFICE, ENGINEER'S | 1.000 | LS |
| 631.1700 | TESTING EQUIPMENT, BITUMINOUS | 1.000 | LS |
| 631.1900 | TESTING EQUIPMENT, GROUT | 1.000 | LS |
| 631.2600 | FIELD OFFICE COMMUNICATIONS (N.A.B.I.) | 3,000.000 | DL |
| 633.1000 | CPM SCHEDULE | 6.000 | EACH |
| 635.1100 | MOBILIZATION/DEMobilIZATION | 1.000 | LS |
| 641.1100 | TRAFFIC CONTROL, ALL-INCLUSIVE | 1.000 | LS |
| 641.1500 | PORTABLE CHANGEABLE MESSAGE SIGN | 2.000 | EACH |
| 641.2200 | TEMPORARY TRAFFIC CONTROL SIGNAL SYSTEM, PORTABLE | 1.000 | EACH |
| 646.2010 | 4 INCH WHITE LINE, WATERBORNE PAINT | 900.000 | LF |
| 646.2111 | 4 INCH YELLOW LINE, WATERBORNE PAINT | 900.000 | LF |
| 649.1100 | GEOTEXTILE FOR ROADBED SEPARATOR | 320.000 | SY |
| 649.3100 | GEOTEXTILE UNDER STONE FILL | 315.000 | SY |
| 651.1500 | TURF ESTABLISHMENT, GENERAL SEED | 1,265.000 | SY |
| 651.1600 | TURF ESTABLISHMENT, SPECIALTY SEED | 128.000 | SY |
| 651.3500 | TOPSOIL | 175.000 | CY |
| 651.4012 | GRUBBING MATERIAL, 12 INCH | 120.000 | SY |
| 653.0100 | EPSC PLAN | 1.000 | LS |
| 653.0200 | MONITORING EPSC PLAN | 10.000 | HR |
| 653.0300 | MAINTENANCE OF EPSC PLAN (N.A.B.I.) | 1,500.000 | DL |
| 653.1200 | STRAW MULCH | 0.600 | TON |
| 653.2001 | ROLLED EROSION CONTROL PRODUCT, TYPE I | 1,400.000 | SY |

| | | | |
|----------|---------------------------------------|---------|------|
| 653.3500 | STABILIZED CONSTRUCTION ENTRANCE | 36.000 | CY |
| 653.4702 | SILT FENCE, TYPE II | 160.000 | LF |
| 653.5000 | BARRIER FENCE | 870.000 | LF |
| 656.3500 | DECIDUOUS SHRUBS | 31.000 | EACH |
| 656.6500 | LANDSCAPE WATERING | 8.000 | MGAL |
| 656.8000 | LANDSCAPE BACKFILL, TRUCK MEASUREMENT | 5.000 | CY |
| 675.2000 | TRAFFIC SIGN, FLAT SHEET ALUMINUM | 2.000 | SF |
| 675.3410 | SQUARE TUBE SIGN POST AND ANCHOR | 48.000 | LF |
| 675.5000 | SIGN REMOVAL, FLAT SHEET ALUMINUM | 3.000 | EACH |
| 675.6000 | RESETTING SIGNS | 1.000 | EACH |
| 690.0300 | PRICE ADJUSTMENT, ASPHALT (N.A.B.I.) | 1.000 | DL |

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.