

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, April 17, 2026**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION: BEGINNING AT A POINT ON US ROUTE 7 APPROXIMATELY 1.655 KM SOUTHERLY OF THE PITTSFORD/BRANDON TOWN LINE AND EXTENDING 1.055 KM NORTHERLY OF THE PITTSFORD/BRANDON TOWNLINE.

TYPE OF CONSTRUCTION: WORK TO BE PERFORMED UNDER THIS CONTRACT INCLUDES THE REMOVAL AND DISPOSAL OF THE EXISTING CONCRETE ROAD, THE WIDENING AND FULL DEPTH RECONSTRUCTION OF US ROUTE 7, REPLACEMENT OF BRIDGE 110 (BOX CULVERT), EXTENSION OF BRIDGES 111, 112 (BOX CULVERTS) GRADING, DRAINAGE, RELOCATION OF AERIAL UTILITIES, PAVING, AND NECESSARY APPROACH WORK.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **October 13, 2028**.

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER'S ESTIMATE: For this proposal the Engineer's Estimate is **Category G**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
<https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting>

VOLUNTARY PRE-BID MEETING/SITE VISIT: Prospective bidders/Contractors are hereby notified that a voluntary pre-bid meeting will be held at 1:00 PM on Monday, March 23, 2026, in the <https://teams.microsoft.com/meet/21941864633880?p=6neN3y2kZlKRH8CXbB>.

ATTENDANCE AT THE PRE-BID MEETING IS NOT REQUIRED to submit a bid. See Proposal Special Provisions for additional information and requirements.

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30 PM on Wednesday, April 8, 2026.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: <https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf>, and must be submitted/uploaded through the iCXWeb website at: <https://vtrans.exevision.com/icx/Index.aspx>

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
<https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications>

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any

contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at: <https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding>

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	1.000	LS
201.3000	THINNING AND TRIMMING	0.025	ACRE
203.1500	COMMON EXCAVATION	74,200.000	CY
203.1600	SOLID ROCK EXCAVATION	7,900.000	CY
203.1700	UNCLASSIFIED EXCAVATION	190.000	CY
203.2700	UNCLASSIFIED CHANNEL EXCAVATION	420.000	CY
203.3000	EARTH BORROW	4,180.000	CY
203.3100	SAND BORROW	30,500.000	CY
204.2000	TRENCH EXCAVATION OF EARTH	5,500.000	CY
204.2100	TRENCH EXCAVATION OF ROCK	60.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000	CY
204.2500	STRUCTURE EXCAVATION	2,315.000	CY
204.3000	GRANULAR BACKFILL FOR STRUCTURES	1,965.000	CY
210.1000	COARSE-MILLING, BITUMINOUS PAVEMENT	425.000	SY
225.0400	RETAINING WALL, PRECAST CONCRETE	1.000	LS
240.0100002	TEMPORARY ROADWAY WIDENING	1.000	LS
240.0100003	TEMPORARY TRAFFIC DIVERSION (BR 110)	1.000	LS
240.0100003	TEMPORARY TRAFFIC DIVERSION (BR 111)	1.000	LS
301.2600	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	2,050.000	CY
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	37,750.000	CY
401.1000	AGGREGATE SURFACE COURSE	335.000	CY
402.1300	AGGREGATE SHOULDERS, RAP	975.000	TON
404.1100	TACK COAT, EMULSIFIED ASPHALT	600.000	CWT
406.0110	BITUMINOUS CONCRETE PAVEMENT, TYPE IS, QA TIER I	17,100.000	TON
406.0310	BITUMINOUS CONCRETE PAVEMENT, TYPE IIIS, QA TIER I	9,800.000	TON
406.0430	BITUMINOUS CONCRETE PAVEMENT, TYPE IVS, QA TIER III	195.000	TON
406.3400	BITUMINOUS CONCRETE PAVEMENT, NON-PAVER PLACED, TYPE IVS	360.000	SY
406.9100	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	1.000	DL
406.9200	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	1.000	DL
406.9300	PAY ADJUSTMENT, BCP, LONGITUDINAL JOINT DENSITY (N.A.B.I.)	1.000	DL
406.9400	PAY ADJUSTMENT, BCP, PAVEMENT ROUGHNESS (N.A.B.I.)	1.000	DL
410.1000	MATERIAL TRANSFER VEHICLE	26,950.000	TON
507.1100	REINFORCING STEEL, LEVEL I (BLACK)	2,180.000	LB
507.1600	DRILLING AND GROUTING DOWELS	40.000	LF
514.1000	WATER REPELLENT, SILANE	12.000	GAL
529.2000	PARTIAL REMOVAL OF STRUCTURE (BR 110)	1.000	EACH
529.2000	PARTIAL REMOVAL OF STRUCTURE (BR 111)	1.000	EACH
529.2000	PARTIAL REMOVAL OF STRUCTURE (BR 112)	1.000	EACH

540.1000	PRECAST CONCRETE STRUCTURE (BR 110) (4267 X 3050 X 37000 BOX CULVERT)	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (BR 111) (1220 X 1525 X 10335 OUTLET EXTENSION)	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (BR 111) (1220 X 1525 X 1205 INLET EXTENSION)	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (BR 112) (1220 X 1525 X 11380 OUTLET EXTENSION)	1.000	LS
540.1500	PRECAST CONCRETE STRUCTURE (1050 MM PIPE HEADWALL)	1.000	EACH
540.1500	PRECAST CONCRETE STRUCTURE (450 MM PIPE HEADWALL)	1.000	EACH
540.1500	PRECAST CONCRETE STRUCTURE (750 MM PIPE HEADWALL)	1.000	EACH
540.1500	PRECAST CONCRETE STRUCTURE (900 MM PIPE HEADWALL)	1.000	EACH
541.2200	CONCRETE, CLASS B	25.000	CY
601.0415	18 INCH PCCSP .064 (2-2/3 × 1/2)	310.000	LF
601.0425	24 INCH PCCSP .064 (2-2/3 × 1/2)	100.000	LF
601.0436	30 INCH PCCSP .079 (2-2/3 × 1/2)	610.000	LF
601.0446	36 INCH PCCSP .079 (2-2/3 × 1/2)	90.000	LF
601.0452	42 INCH PCCSP .109 (2-2/3 × 1/2)	125.000	LF
601.2615	18 INCH CPEP(SL)	495.000	LF
601.2620	24 INCH CPEP(SL)	360.000	LF
601.2625	30 INCH CPEP(SL)	110.000	LF
601.2630	36 INCH CPEP(SL)	110.000	LF
601.6015	18 INCH CSPES .064 (2-2/3 × 1/2)	11.000	EACH
601.6046	36 INCH CSPES .079 (2-2/3 × 1/2)	1.000	EACH
601.6052	42 INCH CSPES .109 (2-2/3 × 1/2)	1.000	EACH
601.7015	18 INCH CPEPES	20.000	EACH
604.1800	PRECAST REINFORCED CONCRETE DI WITH CAST IRON GRATE (1.2 M DIA.) (TRASH RACK)	1.000	EACH
604.2000	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE (1.2 M DIA.)	1.000	EACH
604.2000	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE (1.5 M DIA.)	9.000	EACH
604.4000	CHANGING ELEVATION OF DIS, CATCH BASINS, OR MANHOLES	1.000	EACH
605.1008	UNDERDRAIN PIPE, 8 INCH	5,725.000	LF
605.2008	UNDERDRAIN CARRIER PIPE, 8 INCH	525.000	LF
605.9500	UNDERDRAIN FLUSHING BASIN	17.000	EACH
608.1001	BULLDOZER RENTAL, TYPE I	50.000	HR
608.1500	POWER GRADER RENTAL	50.000	HR
608.2501	ALL-PURPOSE EXCAVATOR RENTAL, TYPE I	100.000	HR
608.3001	POWER BROOM RENTAL, TYPE I	50.000	HR
608.3700	TRUCK RENTAL	125.000	HR
608.4001	LOADER RENTAL, TYPE I	50.000	HR
609.1000	DUST CONTROL WITH WATER	2,600.000	MGAL
609.1500	DUST CONTROL WITH CALCIUM CHLORIDE	15.000	TON
610.1000	GNSS MACHINE CONTROL GRADING	1.000	LS
610.2000	GNSS CONSTRUCTION INSPECTION EQUIPMENT	1.000	EACH
610.2500	GNSS CONSTRUCTION INSPECTION SURFACE MODELS	1.000	LS
613.0602	E-STONE FILL, TYPE II	89.000	CY
613.0603	E-STONE FILL, TYPE III	495.000	CY
613.1001	STONE FILL, TYPE I	225.000	CY
613.1002	STONE FILL, TYPE II	528.000	CY
613.1003	STONE FILL, TYPE III	160.000	CY
614.1000	TEMPORARY RELOCATION OF STREAM (BR 110)	1.000	EACH
614.1000	TEMPORARY RELOCATION OF STREAM (BR 111)	1.000	EACH
614.1000	TEMPORARY RELOCATION OF STREAM (BR 112)	1.000	EACH
614.1000	TEMPORARY RELOCATION OF STREAM (STA. 15+593)	1.000	EACH
617.1100	REMOVE AND RESET MAILBOX, SINGLE SUPPORT	13.000	EACH

617.1200	REMOVE AND RESET MAILBOX, MULTIPLE SUPPORT	9.000	EACH
619.1700	YIELDING MARKER POSTS	41.000	EACH
620.2500	WOVEN WIRE FENCE WITH STEEL POSTS	1,475.000	LF
620.2600	WOVEN WIRE FENCE WITH WOOD POSTS	325.000	LF
620.3000	DRIVE GATE FOR WOVEN WIRE FENCE	1.000	EACH
620.4500	PLANK RAIL FENCE	200.000	LF
620.5000	REMOVING AND RESETTING FENCE	500.000	LF
620.5500	REMOVAL OF EXISTING FENCE	5,100.000	LF
620.8200001	VEHICULAR GATE	1.000	EACH
620.9000	HAND RAILING	160.000	LF
621.0100	REMOVAL OF GUARDRAIL	1,575.000	LF
621.1060	STEEL BEAM GUARDRAIL	2,325.000	LF
621.1530	ANCHOR FOR STEEL BEAM GUARDRAIL, MGS	8.000	EACH
621.3030	MTS, MGS, TANGENT, TL-3	2.000	EACH
621.3130	MTS, MGS, FLARED, TL-3	6.000	EACH
628.1408	PVC SEWER PIPE, 2 INCH	1.000	LF
628.1416	PVC SEWER PIPE, 4 INCH	10.000	LF
630.1000	UNIFORMED TRAFFIC OFFICERS	4,500.000	HR
630.1500	FLAGGERS	13,000.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1600	TESTING EQUIPMENT, CONCRETE	1.000	LS
631.1700	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.1900	TESTING EQUIPMENT, GROUT	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	9,000.000	DL
633.1000	CPM SCHEDULE	30.000	EACH
634.1000	EMPLOYEE TRAINEESHIP	1,040.000	HR
635.1100	MOBILIZATION/DEMOBILIZATION	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE	1.000	LS
641.1500	PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH
646.4060	DURABLE 4 INCH WHITE LINE, RECESSED POLYUREA	20,000.000	LF
646.4160	DURABLE 4 INCH YELLOW LINE, RECESSED POLYUREA	19,000.000	LF
646.4560	DURABLE 8 INCH YELLOW LINE, RECESSED POLYUREA	35.000	LF
646.4960	DURABLE LETTER OR SYMBOL, RECESSED POLYUREA	12.000	EACH
646.6000	TEMPORARY 4 INCH WHITE LINE	59,000.000	LF
646.6100	TEMPORARY 4 INCH YELLOW LINE	56,000.000	LF
646.6900	TEMPORARY LETTER OR SYMBOL	12.000	EACH
646.7600	LINE STRIPING TARGETS	4,200.000	EACH
649.1100	GEOTEXTILE FOR ROADBED SEPARATOR	5,250.000	SY
649.3100	GEOTEXTILE UNDER STONE FILL	3,385.000	SY
651.1500	TURF ESTABLISHMENT, GENERAL SEED	96,750.000	SY
651.1600	TURF ESTABLISHMENT, SPECIALTY SEED	4,250.000	SY
651.1800	TURF ESTABLISHMENT, SOD	475.000	SY
651.3500	TOPSOIL	11,225.000	CY
651.4002	GRUBBING MATERIAL, 2 INCH	430.000	SY
651.4006	GRUBBING MATERIAL, 6 INCH	110.000	SY
651.4012	GRUBBING MATERIAL, 12 INCH	176.000	SY
653.0100	EPSC PLAN	1.000	LS
653.0200	MONITORING EPSC PLAN	700.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	10,000.000	DL
653.1000	HAY MULCH	60.000	TON
653.1200	STRAW MULCH	2.000	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	23,000.000	SY
653.2002	ROLLED EROSION CONTROL PRODUCT, TYPE II	6,750.000	SY
653.2501	CHECK DAM, TYPE I	300.000	CY
653.3500	STABILIZED CONSTRUCTION ENTRANCE	35.000	CY
653.4001	INLET PROTECTION DEVICE, TYPE I	10.000	EACH
653.4003	INLET PROTECTION DEVICE, TYPE III	35.000	CY

653.4500	FILTER BAG	4.000	EACH
653.4701	SILT FENCE, TYPE I	6,500.000	LF
653.4702	SILT FENCE, TYPE II	1,900.000	LF
653.5000	BARRIER FENCE	4,650.000	LF
653.5500	PROJECT DEMARCATION FENCE	14,500.000	LF
653.6000	EROSION LOG	6,500.000	LF
656.2002	EVERGREEN TREES, MEDIUM	48.000	EACH
656.3002	DECIDUOUS TREES, MEDIUM	3.000	EACH
656.3003	DECIDUOUS TREES, LARGE	42.000	EACH
656.3500	DECIDUOUS SHRUBS	241.000	EACH
656.4500	TRANSPLANTING TREES	1.000	EACH
656.5000	TRANSPLANTING SHRUBS	1.000	EACH
656.6500	LANDSCAPE WATERING	130.000	MGAL
656.8000	LANDSCAPE BACKFILL, TRUCK MEASUREMENT	1,940.000	CY
656.8500	TREE PROTECTION	1.000	LS
675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	170.000	SF
675.3410	SQUARE TUBE SIGN POST AND ANCHOR	665.000	LF
675.5000	SIGN REMOVAL, FLAT SHEET ALUMINUM	41.000	EACH
675.5000001	REMOVE PRIVATE SIGN ASSEMBLY, NON-LIGHTED	1.000	EACH
675.6000	RESETTING SIGNS	1.000	EACH
675.6000001	REMOVE AND RESET PRIVATE SIGN ASSEMBLY, NON-LIGHTED	2.000	EACH
676.1000	DELINEATOR WITH STEEL POST	22.000	EACH
676.1200	REMOVAL OF EXISTING DELINEATOR AND POST	24.000	EACH
681.1010	REMOVE AND RELOCATE LANDSCAPE ITEMS (HISTORICAL MONUMENT)	1.000	EACH
681.1010	REMOVE AND RELOCATE LANDSCAPE ITEMS (STONE WALL)	1.000	EACH
681.1010	REMOVE AND RELOCATE LANDSCAPE ITEMS (WALKWAY PAVERS)	1.000	EACH
690.0300	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	1.000	DL
690.0400	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	1.000	DL

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.