

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, May 29, 2026**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION: BRIDGES 55-2 AND 55-3 ARE LOCATED APPROXIMATELY 0.6 MILES SOUTH OF EXIT 15 ALONG INTERSTATE 91 (I-91).

TYPE OF CONSTRUCTION: REPLACEMENT OF BRIDGES 55-2 AND 55-3 WITH A PRECAST CONCRETE STRUCTURE AND CONSTRUCTION OF TEMPORARY CROSSEOVERS, ALONG WITH RELATED APPROACH ROADWAY AND CHANNEL WORK. SURFACE PREPARATION, MILLING, AND PAVING I-91 SOUTHBOUND BETWEEN MILE MARKERS 89.852 AND 91.513.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **October 15, 2028**.

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER'S ESTIMATE: For this proposal the Engineer's Estimate is **Category G**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at: <https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting>

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30 PM on Wednesday, May 20, 2026.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: <https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf>, and must be submitted/uploaded through the iCXWeb website at: <https://vtrans.exevision.com/icx/Index.aspx>

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website. <https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications>

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at: <https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding>

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	1.000	LS
203.1500	COMMON EXCAVATION	6,300.000	CY
203.2700	UNCLASSIFIED CHANNEL EXCAVATION	590.000	CY
203.3000	EARTH BORROW	800.000	CY
203.3100	SAND BORROW	2,500.000	CY
203.3200	GRANULAR BORROW	800.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000	CY
204.2500	STRUCTURE EXCAVATION	44,500.000	CY
204.3000	GRANULAR BACKFILL FOR STRUCTURES	2,700.000	CY
210.1000	COARSE-MILLING, BITUMINOUS PAVEMENT	650.000	SY
210.1200	FINE-MILLING, BITUMINOUS PAVEMENT	40,300.000	SY
213.2010	MILLED RUMBLE STRIPS, SHOULDER	18,800.000	LF
225.0500001	TEMPORARY SUPPORT OF EXCAVATION	1.000	LS
240.0100	TEMPORARY ACCESS ROAD (NORTHBOUND ACCESS)	1.000	LS
240.0100	TEMPORARY ACCESS ROAD (SOUTHBOUND ACCESS)	1.000	LS
240.0100004	DIVIDED HIGHWAY CROSSOVER (NORTHBOUND CROSSOVER)	1.000	LS
240.0100004	DIVIDED HIGHWAY CROSSOVER (SOUTHBOUND CROSSOVER)	1.000	LS
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	3,150.000	CY
401.1000	AGGREGATE SURFACE COURSE	50.000	CY
402.1300	AGGREGATE SHOULDERS, RAP	275.000	TON
404.1100	TACK COAT, EMULSIFIED ASPHALT	600.000	CWT
406.0230	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III	1,025.000	TON
406.0310	BITUMINOUS CONCRETE PAVEMENT, TYPE IIIS, QA TIER I	4,950.000	TON
406.0430	BITUMINOUS CONCRETE PAVEMENT, TYPE IVS, QA TIER III	750.000	TON
406.2400	BITUMINOUS CONCRETE PAVEMENT, SURFACE PREPARATION, TYPE IVS	10.000	TON
406.9100	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	1.000	DL
406.9200	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	1.000	DL
406.9300	PAY ADJUSTMENT, BCP, LONGITUDINAL JOINT DENSITY (N.A.B.I.)	1.000	DL
406.9400	PAY ADJUSTMENT, BCP, PAVEMENT ROUGHNESS (N.A.B.I.)	1.000	DL
410.1000	MATERIAL TRANSFER VEHICLE	6,700.000	TON
514.1000	WATER REPELLENT, SILANE	10.000	GAL
529.1500	REMOVAL OF STRUCTURE (7FT DIA X 290FT LENGTH CMP)	2.000	EACH
540.1000	PRECAST CONCRETE STRUCTURE (18FT X13FT X292FT PRECAST BOX CULVERT)	1.000	LS
541.4500	FLOWABLE FILL	5.000	CY
604.6500	DECOMMISSION DROP INLET	1.000	EACH
608.1500	POWER GRADER RENTAL	10.000	HR
608.2501	ALL-PURPOSE EXCAVATOR RENTAL, TYPE I	10.000	HR
608.3001	POWER BROOM RENTAL, TYPE I	100.000	HR
608.3002	POWER BROOM RENTAL, TYPE II	100.000	HR
608.3700	TRUCK RENTAL	10.000	HR
613.0602	E-STONE FILL, TYPE II	800.000	CY
614.1000	TEMPORARY RELOCATION OF STREAM	1.000	EACH
620.2500	WOVEN WIRE FENCE WITH STEEL POSTS	780.000	LF
620.4000	STEEL BRACE FOR WOVEN WIRE FENCE	12.000	EACH
620.5500	REMOVAL OF EXISTING FENCE	840.000	LF

621.0100	REMOVAL OF GUARDRAIL	600.000	LF
621.0210	REMOVE AND RESET GUARDRAIL	200.000	LF
621.0220	ADJUST HEIGHT OF GUARDRAIL	175.000	LF
621.0300	REPLACE GUARDRAIL BEAM UNIT, W-BEAM	15.000	EACH
621.0360	REPLACE GUARDRAIL POST ASSEMBLY, W-BEAM WITH 6 FOOT POSTS	30.000	EACH
621.1060	STEEL BEAM GUARDRAIL	675.000	LF
621.1500	STEEL BEAM GUARDRAIL OFFSET BLOCK	30.000	EACH
621.1530	ANCHOR FOR STEEL BEAM GUARDRAIL, MGS	4.000	EACH
621.1560	TRAFFIC BARRIER DELINEATOR	100.000	EACH
621.3130	MTS, MGS, FLARED, TL-3	1.000	EACH
630.1000	UNIFORMED TRAFFIC OFFICERS	800.000	HR
630.1500	FLAGGERS	150.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1600	TESTING EQUIPMENT, CONCRETE	1.000	LS
631.1700	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.1900	TESTING EQUIPMENT, GROUT	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	6,000.000	DL
633.1000	CPM SCHEDULE	13.000	EACH
635.1100	MOBILIZATION/DEMOBILIZATION	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE (NORTHBOUND BARREL AND CROSSOVER)	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE (SOUTHBOUND BARREL AND CROSSOVER)	1.000	LS
641.1500	PORTABLE CHANGEABLE MESSAGE SIGN	4.000	EACH
641.1600	PORTABLE ARROW BOARD	4.000	EACH
646.6200	TEMPORARY 6 INCH WHITE LINE	25,750.000	LF
646.6212	TEMPORARY 6 INCH WHITE LINE, TYPE C TAPE	700.000	LF
646.6300	TEMPORARY 6 INCH YELLOW LINE	20,000.000	LF
646.6600	TEMPORARY 12 INCH WHITE LINE	650.000	LF
646.7600	LINE STRIPING TARGETS	4,800.000	EACH
649.1100	GEOTEXTILE FOR ROADBED SEPARATOR	1,965.000	SY
649.3100	GEOTEXTILE UNDER STONE FILL	550.000	SY
651.1500	TURF ESTABLISHMENT, GENERAL SEED	38,100.000	SY
651.1600	TURF ESTABLISHMENT, SPECIALTY SEED (POLLINATOR DRY MIX)	15,500.000	SY
651.1600	TURF ESTABLISHMENT, SPECIALTY SEED (POLLINATOR WET MIX)	1,000.000	SY
651.3500	TOPSOIL	700.000	CY
651.4012	GRUBBING MATERIAL, 12 INCH	400.000	SY
653.0100	EPSC PLAN	1.000	LS
653.0200	MONITORING EPSC PLAN	120.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	3,000.000	DL
653.1000	HAY MULCH	18.000	TON
653.1200	STRAW MULCH	3.000	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	16,050.000	SY
653.2501	CHECK DAM, TYPE I	150.000	CY
653.3500	STABILIZED CONSTRUCTION ENTRANCE	210.000	CY
653.4001	INLET PROTECTION DEVICE, TYPE I	21.000	EACH
653.4002	INLET PROTECTION DEVICE, TYPE II	1.000	EACH
653.4003	INLET PROTECTION DEVICE, TYPE III	40.000	CY
653.4500	FILTER BAG	4.000	EACH
653.4701	SILT FENCE, TYPE I	1,160.000	LF
653.4702	SILT FENCE, TYPE II	1,000.000	LF
653.5000	BARRIER FENCE	700.000	LF
653.5500	PROJECT DEMARICATION FENCE	1,700.000	LF
653.6000	EROSION LOG	2,600.000	LF
656.1200	TUBELINGS	80.000	EACH
656.6500	LANDSCAPE WATERING	12.000	MGAL
656.8000	LANDSCAPE BACKFILL, TRUCK MEASUREMENT	31.000	CY

675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	8.840	SF
675.3100	W-SHAPE STEEL SIGN POST	1,060.000	LB
675.4100	FOUNDATION FOR W-SHAPE STEEL POST, 24 INCH DIAMETER	2.000	EACH
675.5000	SIGN REMOVAL, FLAT SHEET ALUMINUM	6.000	EACH
675.5100	SIGN REMOVAL, EXTRUDED ALUMINUM	3.000	EACH
675.6000	RESETTING SIGNS	3.000	EACH
676.1000	DELINEATOR WITH STEEL POST	7.000	EACH
676.1200	REMOVAL OF EXISTING DELINEATOR AND POST	7.000	EACH
690.0300	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	1.000	DL
690.0400	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	1.000	DL
OPTION - PAVEMENT MARKING OPTIONS - EPOXY PAINT ITEMS			
646.4230	DURABLE 6 INCH WHITE LINE, EPOXY PAINT	13,500.000	LF
646.4330	DURABLE 6 INCH YELLOW LINE, EPOXY PAINT	10,500.000	LF
646.4630	DURABLE 12 INCH WHITE LINE, EPOXY PAINT	325.000	LF
OPTION - PAVEMENT MARKING OPTIONS - POLYUREA ITEMS			
646.4240	DURABLE 6 INCH WHITE LINE, POLYUREA	13,500.000	LF
646.4340	DURABLE 6 INCH YELLOW LINE, POLYUREA	10,500.000	LF
646.4640	DURABLE 12 INCH WHITE LINE, POLYUREA	325.000	LF

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.