

Table of Contents	1
Addendum 1 Letter	2
Addendum 1 Plans	3
Addendum 1 Project Special Provisions	5



---

**State of Vermont**  
**Contract Administration**  
Barre City Place  
219 North Main Street, Suite 105  
Barre VT 05641  
<http://vtrans.vermont.gov>

*Agency of Transportation  
Finance & Administration*  
[phone] 802-622-1285  
[ttd] 800-253-0191

May 4, 2026

**CO3269** – SUNDERLAND BM20102 & SUNDERLAND NH CULV(122)

**ADDENDUM #1**

Bidders:

Changes have been made to the documents located on the Bid Opportunity website as noted below:

**REVISED:**

Plan Sheet 9 and 38.

Special Provisions Page 1

The Scheule of items in the Proposal and Invitation for Bids.

- Item 540.1000 Precast Concrete Structure (14 FT X 8 FT X 125 FT BOX CULVERT)(BM20102)
- Item 540.1000 Precast Concrete Structure (14 FT X 8 FT X 125 FT BOX CULVERT)(NH CULV(122))

**ADDED:**

Special Provisions Page 19

**DELETED:** None.

**VTrans Mission and Vision**

Through excellent customer service, provide for the safe and efficient movement of people and goods.  
A safe, reliable, and multimodal transportation system that grows the economy, is affordable to use and operate, and serves vulnerable populations.



# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						1011 - ROADWAY	1051 - EROSION CONTROL	1211 - BRIDGE NO. 1	1999 - FULL C.E. ITEMS	3041 - LANDSCAPING	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								157,920.00			157,920.00		DL	INCENTIVE OR DISINCENTIVE (N.A.B.I.)	199.8101				
						1.00					1.00		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (BRIDGE 19-5)	201.1000				EARTHWORK SUMMARY
						1,625.00					1,625.00		CY	COMMON EXCAVATION	203.1500				FILL AVAILABLE
								350.00			350.00		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.2700		1,625.0	CY	COMMON EXCAVATION(1625 X 1 0)
													CY	UNCLASSIFIED CHANNEL EXCAVATION	203.2700		105.0	CY	UNCLASSIFIED CHANNEL EXCAVATION(350 X 0 3)
						380.00					380.00		CY	GRANULAR BORROW	203.3200		390.0	CY	STRUCTURE EXCAVATION(1300 X 0 3)
						1.00					1.00		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.2200		80.0	CY	ROUNDING
								1,300.00			1,300.00		CY	STRUCTURE EXCAVATION	204.2500		2,200.0	CY	TOTAL FILL AVAILABLE
								400.00			400.00		CY	GRANULAR BACKFILL FOR STRUCTURES	204.3000				FILL REQUIRED
						675.00					675.00		SY	COARSE-MILLING, BITUMINOUS PAVEMENT	210.1000		69.0	CY	FACTORED FILL REQUIRED (60 X 1 15)
						1,450.00					1,450.00		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.3500		1.0	CY	ROUNDING
						21.00					21.00		OWT	TACK COAT, EMULSIFIED ASPHALT	404.1100		70.0	CY	TOTAL FILL REQUIRED
						315.00					315.00		TON	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III	406.0230				BORROW OR WASTE
						270.00					270.00		TON	BITUMINOUS CONCRETE PAVEMENT, TYPE IVS, QA TIER III	406.0430		2,130.0	CY	WASTE
						1.00					1.00		DL	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	406.9100				
						1.00					1.00		DL	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	406.9200				
								4.00			4.00		GAL	WATER REPELLENT, SILANE	514.1000				
								1.00			1.00		EACH	REMOVAL OF STRUCTURE (8 2 FT X 5 8 FT X 162 FT CGMPPA)	529.1500				
								1.00			1.00		LS	PRECAST CONCRETE STRUCTURE (14 FT X 8 FT X 125 FT BOX CULVERT)(BM 20102)	540.1000				
								250.00			250.00		CY	E-STONE FILL, TYPE II	613.0602				
								10.00			10.00		CY	STONE FILL, TYPE I	613.1001				
								120.00			120.00		CY	STONE FILL, TYPE II	613.1002				
								1.00			1.00		EACH	TEMPORARY RELOCATION OF STREAM (BRIDGE 19-5)	614.1000				
						104.00					104.00		HR	UNIFORMED TRAFFIC OFFICERS	630.1000				
						152.00					152.00		HR	FLAGGERS	630.1500				
									1.00		1.00		LS	FIELD OFFICE, ENGINEER'S (BRIDGE 19-5)	631.1000				
									1.00		1.00		LS	TESTING EQUIPMENT, BITUMINOUS (BRIDGE 19-5)	631.1700				
									1.00		1.00		LS	TESTING EQUIPMENT, GROUT (BRIDGE 19-5)	631.1900				
									1,500.00		1,500.00		DL	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	631.2000				
						1.00					1.00		LS	MOBILIZATION/DEMobilIZATION (BRIDGE 19-5)	635.1100				
						1.00					1.00		LS	TRAFFIC CONTROL, ALL INCLUSIVE (BRIDGE 19-5)	641.1100				
						6.00					6.00		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.1500				
						2.00					2.00		EACH	TEMPORARY TRAFFIC CONTROL SIGNAL SYSTEM, PORTABLE	641.2200				
						750.00					750.00		LF	6 INCH WHITE LINE, WATERBORNE PAINT	646.2141				
						750.00					750.00		LF	8 INCH YELLOW LINE, WATERBORNE PAINT	646.2151				
						400.00					400.00		SF	PAVEMENT MARKING MASK	646.8600				
						2,000.00					2,000.00		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.1100				
								360.00			360.00		SY	GEOTEXTILE UNDER STONE FILL	649.3100				
							2,100.00				2,100.00		SY	TURF ESTABLISHMENT, SPECIALTY SEED (POLLINATOR DRY MIX)	651.1600				
							230.00				230.00		CY	TOPSOIL	651.3500				
							50.00				50.00		SY	GRUBBING MATERIAL, 12 INCH	651.4012				
							1.00				1.00		LS	EPSC PLAN (BRIDGE 19-5)	653.0100				

ADDENDUM	REVISION	PLOT DATE	DESCRIPTION	BY
I	I	05/04/2026	REVISED ITEM SUPPLEMENTAL DESCRIPTION	TH



PROJECT NAME:	SUNDERLAND	FILE NAME:	z20bl55qs.dgn	PLOT DATE:	5/4/2026
PROJECT NUMBER:	BM 20102	PROJECT LEADER:	A. STOCKIN	DRAWN BY:	M. HERMIS
		DESIGNED BY:	M. GROTE	CHECKED BY:	T. HIGGINSON
		QUANTITY SHEET I		SHEET	9 OF 66

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					1011 - ROADWAY	1061 - EROSION CONTROL	1211 - BRIDGE NO. 1	1999 - FULL C.E. ITEMS	3041 - LANDSCAPING	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					1.00					1.00		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (BRIDGE 19-7)	201.1000				
					1,850.00					1,850.00		CY	COMMON EXCAVATION	203.1500				
							450.00			450.00		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.2700				
					500.00					500.00		CY	GRANULAR BORROW	203.3200				
					1.00					1.00		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.2200				
							1,450.00			1,450.00		CY	STRUCTURE EXCAVATION	204.2500				
							400.00			400.00		CY	GRANULAR BACKFILL FOR STRUCTURES	204.3000				
					775.00					775.00		SY	COARSE-MILLING, BITUMINOUS PAVEMENT	210.1000				
					1,600.00					1,600.00		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.3500				
					55.00					55.00		CY	AGGREGATE SURFACE COURSE	401.1000				
					23.00					23.00		OWT	TACK COAT, EMULSIFIED ASPHALT	404.1100				
					361.00					361.00		TON	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III	406.0230				
					302.00					302.00		TON	BITUMINOUS CONCRETE PAVEMENT, TYPE IVS, QA TIER III	406.0430				
					1.00					1.00		DL	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	406.9100				
					1.00					1.00		DL	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	406.9200				
							4.00			4.00		GAL	WATER REPELLENT, SILANE	514.1000				
							1.00			1.00		EACH	REMOVAL OF STRUCTURE (7 FT DIA. X 120 FT CGMPP)	529.1500				
							1.00			1.00		LS	PRECAST CONCRETE STRUCTURE (14 FT X 8 FT X 125 FT BOX CULVERT)(NH CULV(122))	540.1000				
							270.00			270.00		CY	E-STONE FILL, TYPE II	613.0602				
							10.00			10.00		CY	STONE FILL, TYPE I	613.1001				
							225.00			225.00		CY	STONE FILL, TYPE II	613.1002				
							1.00			1.00		EACH	TEMPORARY RELOCATION OF STREAM (BRIDGE 19-7)	614.1000				
					560.00					560.00		LF	REMOVAL OF GUARDRAIL	621.0100				
					575.00					575.00		LF	STEEL BEAM GUARDRAIL	621.1060				
					2.00					2.00		EACH	MTS, MGS, TANGENT, TL-3	621.3030				
					104.00					104.00		HR	UNIFORMED TRAFFIC OFFICERS	630.1000				
					152.00					152.00		HR	FLAGGERS	630.1500				
								1.00		1.00		LS	FIELD OFFICE, ENGINEER'S (BRIDGE 19-7)	631.1000				
								1.00		1.00		LS	TESTING EQUIPMENT, BITUMINOUS (BRIDGE 19-7)	631.1700				
								1.00		1.00		LS	TESTING EQUIPMENT, GROUT (BRIDGE 19-7)	631.1900				
								1,500.00		1,500.00		DL	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	631.2600				
					1.00					1.00		LS	MOBILIZATION/DEMobilIZATION (BRIDGE 19-7)	635.1100				
					1.00					1.00		LS	TRAFFIC CONTROL, ALL INCLUSIVE (BRIDGE 19-7)	641.1100				
					750.00					750.00		LF	8 INCH WHITE LINE, WATERBORNE PAINT	646.2141				
					750.00					750.00		LF	8 INCH YELLOW LINE, WATERBORNE PAINT	646.2151				
					2,100.00					2,100.00		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.1100				
							510.00			510.00		SY	GEOTEXTILE UNDER STONE FILL	649.3100				
						1,700.00				1,700.00		SY	TURF ESTABLISHMENT, SPECIALTY SEED (POLLINATOR DRY MIX)	651.1600				
						190.00				190.00		CY	TOPSOIL	651.3500				
						100.00				100.00		SY	GRUBBING MATERIAL, 12 INCH	651.4012				
						1.00				1.00		LS	EPSC PLAN (BRIDGE 19-7)	653.0100				

ADDENDUM	REVISION	PLOT DATE	DESCRIPTION	BY
1	I	05/04/2026	REVISED ITEM SUPPLEMENTAL DESCRIPTION	TH



PROJECT NAME: SUNDERLAND  
PROJECT NUMBER: NH CULV(122)

FILE NAME: z23b027qs.dgn  
PROJECT LEADER: A. STOCKIN  
DESIGNED BY: M. GROTE  
QUANTITY SHEET 1

PLOT DATE: 5/4/2026  
DRAWN BY: M. HERMIS  
CHECKED BY: T. HIGGINSON  
SHEET 38 OF 66

SPECIAL PROVISIONS

1. NOTICE TO BIDDERS – CONTRACT COMPLETION DATE. This Contract shall be completed on or before October 30, 2026.
2. NOTICE TO BIDDERS – INCENTIVE/DISINCENTIVE (I/D). In accordance with Subsection 108.10 and as described below, there shall be an Incentive/Disincentive period on this Contract.

- (a) Dates and Meetings. The allowable I/D period to construct both Sunderland BM 20102 & Sunderland NH CULV(122) shall start at 7:00 a.m. and end 14 days later by 6:59 a.m. This single 14-day work period is herein defined as the I/D period. The begin construction date for the I/D period shall be determined by the Contractor. However, in no case shall the I/D period begin before 7:00 a.m. on August 12, 2026, and it shall end no later than 6:59 a.m. on October 10, 2026.

During the I/D period, the Contractor will be allowed to work on the project for 24 hours per day, 7 days per week, including holiday periods. Night work will be allowed during the I/D period. See Notice to Bidders No. 4 for additional information and requirements regarding night work.

- (b) Identified Work. All work identified below shall be completed before the end of the I/D period:
  - (1) Removal of the existing culverts as detailed on the Plans;
  - (2) Installation and backfill of precast concrete box culvert units, precast headwalls, precast wingwalls, precast cut off walls, and precast retention sills;
  - (3) Roadway embankment, subbase and both base course pavement lifts;
  - (4) Installation of guardrail.
  - (5) Open to two, 12-foot lanes of traffic, including temporary road markings, as needed;

Work outside of the I/D period may include activities such as EPSC, traffic control, preparatory work, work that does not require a permanent closure of the shoulder or lane prior to the I/D period, and final punch list items.

Outside of the I/D period, no daytime lane closures will be allowed. Shoulder closures are permitted during daytime hours.

41. **NOTICE TO BIDDERS – SUBSECTION 103.04(e)**. Subsection 103.04(e) is hereby modified by deleting the sentence “Limits of coverage shall not be less than \$2,000,000 per occurrence or claim and \$2,000,000 in the aggregate.” from the second paragraph and replacing it with the sentence “Limits of coverage shall not be less than \$1,000,000 per occurrence or claim and \$1,000,000 in the aggregate.”.