

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, May 22, 2026**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION: LOCATED IN THE TOWN OF NORTHFIELD ON VT ROUTE 12, BRIDGE 60 OVER DOG RIVER, APPROXIMATELY 1.1 MILES NORTH OF THE JUNCTION WITH VT ROUTE 12A SOUTH.

TYPE OF CONSTRUCTION: REMOVAL AND REPLACEMENT OF BRIDGE NO, 60 WITH RELATED APPROACH ROADWAY AND CHANNEL WORK.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **October 29, 2027**.

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER's ESTIMATE: For this proposal the Engineer's Estimate is **Category G**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
<https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting>

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30 PM on Wednesday, May 13, 2026.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: <https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf>, and must be submitted/uploaded through the iCXWeb website at: <https://vtrans.exevision.com/icx/Index.aspx>

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
<https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications>

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at:
<https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding>

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
199.8101	INCENTIVE OR DISINCENTIVE (N.A.B.I.)	225,000.00 0	DL
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	1.000	LS
203.1500	COMMON EXCAVATION	1,200.000	CY
203.1600	SOLID ROCK EXCAVATION	134.000	CY
203.1700	UNCLASSIFIED EXCAVATION	15.000	CY
203.2700	UNCLASSIFIED CHANNEL EXCAVATION	1,950.000	CY
204.2000	TRENCH EXCAVATION OF EARTH	1,000.000	CY
204.2100	TRENCH EXCAVATION OF ROCK	1.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000	CY
204.2500	STRUCTURE EXCAVATION	940.000	CY
204.3000	GRANULAR BACKFILL FOR STRUCTURES	760.000	CY
210.1000	COARSE-MILLING, BITUMINOUS PAVEMENT	230.000	SY
225.0300002	SOLDIER PILES FOR SOLDIER PILE AND LAGGING WALL	376.000	LF
225.0300003	DRILLED HOLE IN EARTH FOR SOLDIER PILE AND LAGGING WALL	306.000	LF
225.0300004	DRILLED HOLE IN ROCK FOR SOLDIER PILE AND LAGGING WALL	70.000	LF
225.0300005	TIMBER LAGGING FOR SOLDIER PILE AND LAGGING WALL	425.000	SF
225.0300006	CONCRETE FACING FOR SOLDIER PILE AND LAGGING WALL	591.000	SF
225.0500	RETAINING WALL, CONCRETE (WINGWALL 1)	1.000	LS
225.0500	RETAINING WALL, CONCRETE (WINGWALL 4)	1.000	LS
230.0010	DISPOSAL OF CONTAMINATED MATERIALS (N.A.B.I.) ((PCF)(N.A.B.I.))	145,792.00 0	DL
230.0010	DISPOSAL OF CONTAMINATED MATERIALS (N.A.B.I.) (DEVELOPMENT SOIL)	538,624.00 0	DL
230.0020	REUSE OF CONTAMINATED MATERIALS	500.000	CY
230.0030	PROJECT OPERATIONS PLAN	1.000	LS
230.0040	PROJECT OPERATIONS COMPLETION REPORT	1.000	LS
230.0050	ENVIRONMENTAL OVERSIGHT ((NON-PCF))	240.000	HR
230.0050	ENVIRONMENTAL OVERSIGHT ((PCF))	240.000	HR
230.0060	MANAGEMENT OF CONTAMINATED GROUNDWATER (PCF)	1.000	LS
240.0100	TEMPORARY ACCESS ROAD	1.000	LS
240.0200	TEMPORARY CAUSEWAY	1.000	LS
250.0100	CONSTRUCTION VIBRATION AND CRACK MONITORING	1.000	LS
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	848.000	CY
404.1100	TACK COAT, EMULSIFIED ASPHALT	100.000	CWT
406.0230	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III	155.000	TON
406.0330	BITUMINOUS CONCRETE PAVEMENT, TYPE IIIS, QA TIER III	136.000	TON
406.0430	BITUMINOUS CONCRETE PAVEMENT, TYPE IVS, QA TIER III	220.000	TON
406.3400	BITUMINOUS CONCRETE PAVEMENT, NON-PAVER PLACED, TYPE IVS	310.000	SY
406.9100	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	1.000	DL
406.9200	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	1.000	DL
501.3700	PERFORMANCE-BASED CONCRETE, CLASS PCD	355.000	CY
501.3800	PERFORMANCE-BASED CONCRETE, CLASS PCS	145.000	CY
505.1650	STEEL PILING, HP 12 x 84	364.000	LF
506.5500	STRUCTURAL STEEL, PLATE GIRDER	335,100.00 0	LB
507.1100	REINFORCING STEEL, LEVEL I	7,800.000	LB

507.1200	REINFORCING STEEL, LEVEL II	107,200.00	LB
		0	
508.1500	SHEAR CONNECTORS (1974 - 7/8 X 7IN)	1.000	LS
509.1500	CONCRETE BRIDGE DECK SURFACE PREPARATION	6,144.000	SF
510.4000	PRESTRESSED CONCRETE DECK PANELS	5,568.000	SF
514.1000	WATER REPELLENT, SILANE	106.000	GAL
516.1000	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	76.000	LF
524.1100	JOINT SEALER, HOT POURED	76.000	LF
525.5200	BRIDGE RAILING, TEXAS RAIL WITH WINDOWS	329.000	LF
529.2000	PARTIAL REMOVAL OF STRUCTURE	1.000	EACH
541.2800	CONCRETE, CLASS SCC	79.000	CY
541.4500	FLOWABLE FILL	2.000	CY
546.1000	PRE-EXCAVATION OF ABUTMENT PILES, EARTH	224.000	LF
546.2000	PRE-EXCAVATION OF ABUTMENT PILES, ROCK	98.000	LF
546.3000	PRE-EXCAVATION FOR PILES OBSTRUCTION DRILLING AND REMOVAL	30.000	LF
546.4000	FURNISHING EQUIPMENT FOR PRE-EXCAVATION FOR PILES	1.000	LS
601.0920	24 INCH CPEP	111.000	LF
601.2625	30 INCH CPEP(SL)	70.000	LF
601.2630	36 INCH CPEP(SL)	63.000	LF
601.7025	30 INCH CPEPES	1.000	EACH
601.7030	36 INCH CPEPES	1.000	EACH
604.1800	PRECAST REINFORCED CONCRETE DI WITH CAST IRON GRATE	2.000	EACH
604.2000	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE	5.000	EACH
604.4000	CHANGING ELEVATION OF DIS, CATCH BASINS, OR MANHOLES	2.000	EACH
604.4200	CHANGING ELEVATION OF SEWER MANHOLES	1.000	EACH
604.4504	CAST IRON GRATE WITH FRAME, TYPE D	3.000	EACH
605.1006	UNDERDRAIN PIPE, 6 INCH	156.000	LF
613.0601	E-STONE FILL, TYPE I	180.000	CY
613.0604	E-STONE FILL, TYPE IV	240.000	CY
613.1004	STONE FILL, TYPE IV	840.000	CY
614.1000	TEMPORARY RELOCATION OF STREAM	1.000	EACH
616.2100	VERTICAL GRANITE CURB	280.000	LF
616.4000	REMOVING AND RESETTING CURB	33.000	LF
616.4100	REMOVAL OF EXISTING CURB	37.000	LF
618.1005	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	170.000	SY
618.1008	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	61.000	SY
618.3000	DETECTABLE WARNING SURFACE	25.000	SF
620.1006	CHAIN-LINK FENCE, 6 FOOT	70.000	LF
620.5500	REMOVAL OF EXISTING FENCE	20.000	LF
621.0100	REMOVAL OF GUARDRAIL	100.000	LF
625.2004	SLEEVES FOR UTILITIES, PVC, 4 INCH	20.000	LF
625.3000	SLEEVES FOR UTILITIES, STEEL (32 INCH)	45.000	LF
625.4000	CONCRETE ENCASED CONDUIT	118.000	LF
625.5000	DIRECT BURIAL CONDUIT	363.000	LF
625.6000	WIRED CONDUIT	481.000	LF
625.7010	JUNCTION BOX	2.000	EACH
629.1700002	WATER MAIN ON BRIDGE, ALL-INCLUSIVE	1.000	LS
629.2800	ADJUST ELEVATION OF VALVE BOX	7.000	EACH
629.4300	TRANSFER TO NEW SYSTEM, WATER, ALL-INCLUSIVE	1.000	LS
630.1500	FLAGGERS	1,500.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1600	TESTING EQUIPMENT, CONCRETE	1.000	LS
631.1700	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	3,000.000	DL
632.1000	RAILROAD FLAGGERS (N.A.B.I.)	14,000.000	DL
633.1000	CPM SCHEDULE	14.000	EACH

634.1000	EMPLOYEE TRAINEESHIP	520.000	HR
635.1100	MOBILIZATION/DEMOBILIZATION	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE	1.000	LS
641.1200	MAINTENANCE OF PEDESTRIAN TRAFFIC	1.000	LS
641.1500	PORTABLE CHANGEABLE MESSAGE SIGN	3.000	EACH
646.4030	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	1,650.000	LF
646.4130	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	1,120.000	LF
646.4230	DURABLE 6 INCH WHITE LINE, EPOXY PAINT	1,280.000	LF
646.4930	DURABLE LETTER OR SYMBOL, EPOXY PAINT	12.000	EACH
646.5020	DURABLE CROSSWALK MARKING, THERMOPLASTIC	80.000	LF
649.3100	GEOTEXTILE UNDER STONE FILL	685.000	SY
651.1500	TURF ESTABLISHMENT, GENERAL SEED	403.000	SY
651.1600	TURF ESTABLISHMENT, SPECIALTY SEED	1,477.000	SY
651.3500	TOPSOIL	45.000	CY
651.4000	GRUBBING MATERIAL	510.000	SY
653.0100	EPSC PLAN	1.000	LS
653.0200	MONITORING EPSC PLAN	80.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	3,000.000	DL
653.1000	HAY MULCH	1.000	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	282.000	SY
653.3500	STABILIZED CONSTRUCTION ENTRANCE	170.000	CY
653.4002	INLET PROTECTION DEVICE, TYPE II	10.000	EACH
653.4500	FILTER BAG	3.000	EACH
653.4702	SILT FENCE, TYPE II	260.000	LF
653.5000	BARRIER FENCE	600.000	LF
656.3002	DECIDUOUS TREES, MEDIUM	4.000	EACH
656.3500	DECIDUOUS SHRUBS	80.000	EACH
656.6500	LANDSCAPE WATERING	11.000	MGAL
656.8000	LANDSCAPE BACKFILL, TRUCK MEASUREMENT	16.000	CY
656.8500	TREE PROTECTION	1.000	LS
675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	47.000	SF
675.3410	SQUARE TUBE SIGN POST AND ANCHOR	108.000	LF
675.4300	FOUNDATION FOR TUBULAR STEEL POST	2.000	EACH
675.5000	SIGN REMOVAL, FLAT SHEET ALUMINUM	1.000	EACH
675.6000	RESETTING SIGNS	4.000	EACH
675.6000002	REMOVE AND RESET PRIVATE SIGN ASSEMBLY, LIGHTED	1.000	EACH
676.1000	DELINEATOR WITH STEEL POST	4.000	EACH
679.2400	REMOVE STREET LIGHT ASSEMBLY	4.000	EACH
679.2500	REMOVE AND RESET LIGHT POLE (WESCO)	1.000	EACH
679.4600001	ORNAMENTAL STREET LIGHT ASSEMBLY	6.000	EACH
679.4600002	ORNAMENTAL STREET LIGHT FOUNDATION	6.000	EACH
690.0300	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	1.000	DL

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.