

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, June 19, 2026**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION: Located in the Town of Weston on Vermont Route 100 at Mile Marker 1.036 over an unnamed tributary to the West River.

TYPE OF CONSTRUCTION: Work to be performed under this project includes the removal of a concrete box culvert, relocation of channel, and installation of a precast concrete box culvert with associated roadway and channel work.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **September 15, 2027**.

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER's ESTIMATE: For this proposal the Engineer's Estimate is **Category D**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
<https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting>

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30 PM on Wednesday, June 10, 2026.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: <https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf>, and must be submitted/uploaded through the iCXWeb website at: <https://vtrans.exevision.com/icx/Index.aspx>

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
<https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications>

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at:
<https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding>

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
199.8101	INCENTIVE OR DISINCENTIVE (N.A.B.I.)	104,640.00 0	DL
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	1.000	LS
203.1500	COMMON EXCAVATION	390.000	CY
203.2700	UNCLASSIFIED CHANNEL EXCAVATION	360.000	CY
203.3200	GRANULAR BORROW	295.000	CY
204.2000	TRENCH EXCAVATION OF EARTH	55.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000	CY
204.2500	STRUCTURE EXCAVATION	1,455.000	CY
204.3000	GRANULAR BACKFILL FOR STRUCTURES	470.000	CY
210.1000	COARSE-MILLING, BITUMINOUS PAVEMENT	160.000	SY
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	510.000	CY
401.1000	AGGREGATE SURFACE COURSE	25.000	CY
404.1100	TACK COAT, EMULSIFIED ASPHALT	6.000	CWT
406.0230	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III	180.000	TON
406.0430	BITUMINOUS CONCRETE PAVEMENT, TYPE IVS, QA TIER III	65.000	TON
406.9100	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	1.000	DL
406.9200	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	1.000	DL
514.1000	WATER REPELLENT, SILANE	4.000	GAL
529.2000	PARTIAL REMOVAL OF STRUCTURE	1.000	EACH
540.1000	PRECAST CONCRETE STRUCTURE (16 FT X 8 FT X 140 FT BOX CULVERT)	1.000	LS
541.4500	FLOWABLE FILL	90.000	CY
543.1500	CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE (MOMENT SLAB)	15.000	EACH
601.0015	18 INCH CSP .064 (2-2/3 × 1/2)	80.000	LF
609.1000	DUST CONTROL WITH WATER	1.000	MGAL
613.0602	E-STONE FILL, TYPE II	300.000	CY
613.0603	E-STONE FILL, TYPE III	205.000	CY
613.1001	STONE FILL, TYPE I	40.000	CY
614.1000	TEMPORARY RELOCATION OF STREAM	1.000	EACH
621.0100	REMOVAL OF GUARDRAIL	320.000	LF
621.1060	STEEL BEAM GUARDRAIL	420.000	LF
621.1520	ANCHOR FOR STEEL BEAM GUARDRAIL	3.000	EACH
621.2400	TEMPORARY TRAFFIC BARRIER	300.000	LF
630.1500	FLAGGERS	240.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1600	TESTING EQUIPMENT, CONCRETE	1.000	LS
631.1700	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.1900	TESTING EQUIPMENT, GROUT	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	3,000.000	DL
633.1000	CPM SCHEDULE	5.000	EACH
635.1100	MOBILIZATION/DEMOBILIZATION	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE	1.000	LS
641.1500	PORTABLE CHANGEABLE MESSAGE SIGN	3.000	EACH
641.2200	TEMPORARY TRAFFIC CONTROL SIGNAL SYSTEM, PORTABLE	1.000	EACH
646.4030	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	480.000	LF

646.4130	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	480.000	LF
646.6000	TEMPORARY 4 INCH WHITE LINE	1,100.000	LF
646.6800	TEMPORARY 24 INCH STOP BAR	24.000	LF
646.8600	PAVEMENT MARKING MASK	450.000	SF
651.1500	TURF ESTABLISHMENT, GENERAL SEED	1,100.000	SY
651.3500	TOPSOIL	130.000	CY
651.4012	GRUBBING MATERIAL, 12 INCH	160.000	SY
653.0100	EPSC PLAN	1.000	LS
653.0200	MONITORING EPSC PLAN	40.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	4,000.000	DL
653.1000	HAY MULCH	0.500	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	450.000	SY
653.3500	STABILIZED CONSTRUCTION ENTRANCE	20.000	CY
653.4500	FILTER BAG	1.000	EACH
653.4702	SILT FENCE, TYPE II	650.000	LF
653.5000	BARRIER FENCE	680.000	LF
656.3500	DECIDUOUS SHRUBS	90.000	EACH
656.6500	LANDSCAPE WATERING	12.000	MGAL
656.8000	LANDSCAPE BACKFILL, TRUCK MEASUREMENT	16.000	CY
675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	0.840	SF
675.3410	SQUARE TUBE SIGN POST AND ANCHOR	24.000	LF
675.5000	SIGN REMOVAL, FLAT SHEET ALUMINUM	1.000	EACH
676.1000	DELINEATOR WITH STEEL POST	3.000	EACH
690.0300	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	1.000	DL

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.