

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, September 04, 2026**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION: LOCATED ON VT ROUTE 30 IN JAMAICA, OVER THE WINHALL RIVER APPROXIMATELY 0.9 MILES NORTH OF THE JUNCTION WITH VT ROUTE 100.

TYPE OF CONSTRUCTION: REMOVAL OF EXISTING TEMPORARY BRIDGE AND REPLACEMENT WITH A STEEL GIRDER BRIDGE WITH ASSOCIATED CHANNEL, ROADWAY, AND APPROACH WORK.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **June 30, 2028**.

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER's ESTIMATE: For this proposal the Engineer's Estimate is **Category E**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
<https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting>

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30 PM on Wednesday, August 26, 2026.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: <https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf>, and must be submitted/uploaded through the iCXWeb website at: <https://vtrans.exevision.com/icx/Index.aspx>

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
<https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications>

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at:
<https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding>

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
199.8121	LIQUIDATED DAMAGES, INTERIM COMPLETION DATE (N.A.B.I.) (BRIDGE OPENING)	1.000	DL
199.8121	LIQUIDATED DAMAGES, INTERIM COMPLETION DATE (N.A.B.I.) (TEMPORARY BRIDGE REMOVAL)	1.000	DL
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	1.000	LS
203.1500	COMMON EXCAVATION	4,200.000	CY
203.2700	UNCLASSIFIED CHANNEL EXCAVATION	1,900.000	CY
203.2800	EXCAVATION OF SURFACES AND PAVEMENTS	290.000	CY
204.2000	TRENCH EXCAVATION OF EARTH	50.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000	CY
204.2500	STRUCTURE EXCAVATION	265.000	CY
204.3000	GRANULAR BACKFILL FOR STRUCTURES	180.000	CY
210.1000	COARSE-MILLING, BITUMINOUS PAVEMENT	720.000	SY
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	3,600.000	CY
401.1000	AGGREGATE SURFACE COURSE	395.000	CY
404.1100	TACK COAT, EMULSIFIED ASPHALT	40.000	CWT
406.0230	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III	880.000	TON
406.0230001	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, LOW RISK	588.000	TON
406.0430	BITUMINOUS CONCRETE PAVEMENT, TYPE IVS, QA TIER III	575.000	TON
406.3400	BITUMINOUS CONCRETE PAVEMENT, NON-PAVER PLACED, TYPE IVS	364.000	SY
406.9100	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	1.000	DL
406.9200	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	1.000	DL
501.3700	PERFORMANCE-BASED CONCRETE, CLASS PCD (FPQ)	190.000	CY
501.3800	PERFORMANCE-BASED CONCRETE, CLASS PCS (FPQ)	150.000	CY
505.1800	STEEL PILING, HP 14 x 89	540.000	LF
505.4500	DYNAMIC PILE LOADING TEST	2.000	EACH
506.5500	STRUCTURAL STEEL, PLATE GIRDER (HYBRID)(METALIZED)(FPQ)	194,900.00 0	LB
507.1100	REINFORCING STEEL, LEVEL I	1,180.000	LB
507.1100	REINFORCING STEEL, LEVEL I (EPOXY COATED)	7,080.000	LB
507.1200	REINFORCING STEEL, LEVEL II	72,830.000	LB
508.1500	SHEAR CONNECTORS	1.000	LS
509.1500	CONCRETE BRIDGE DECK SURFACE PREPARATION	510.000	SF
514.1000	WATER REPELLENT, SILANE	15.000	GAL
514.1000001	CONCRETE CRACK SEALING, METHYL METHACRYLATE	5.000	GAL
516.1000	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG (FPQ)	64.000	LF
524.1100	JOINT SEALER, HOT POURED (FPQ)	64.000	LF
525.3130	BRIDGE RAILING, GALVANIZED 3 RAIL BOX BEAM (FPQ)	246.000	LF
529.1500	REMOVAL OF STRUCTURE (TEMPORARY BRIDGE, 4900 SF)	1.000	EACH
541.2200	CONCRETE, CLASS B	10.000	CY
546.1500	PRE-EXCAVATION FOR PILES, EARTH	160.000	LF
546.2500	PRE-EXCAVATION FOR PILES, ROCK	50.000	LF
546.4000	FURNISHING EQUIPMENT FOR PRE-EXCAVATION FOR PILES	1.000	LS
601.2640	48 INCH CPEP(SL)	49.000	LF
608.2501	ALL-PURPOSE EXCAVATOR RENTAL, TYPE I	20.000	HR
609.1000	DUST CONTROL WITH WATER	1.000	MGAL
613.0604	E-STONE FILL, TYPE IV	735.000	CY

613.1001	STONE FILL, TYPE I	20.000	CY
613.1004	STONE FILL, TYPE IV	940.000	CY
616.2702	CAST-IN-PLACE CONCRETE CURB, TYPE B	129.000	LF
621.0100	REMOVAL OF GUARDRAIL	748.000	LF
621.1060	STEEL BEAM GUARDRAIL	504.000	LF
621.3130	MTS, MGS, FLARED, TL-3	3.000	EACH
621.8130	GUARDRAIL APPROACH SECTION, 3 RAIL BOX BEAM	4.000	EACH
630.1000	UNIFORMED TRAFFIC OFFICERS	100.000	HR
630.1500	FLAGGERS	2,200.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1600	TESTING EQUIPMENT, CONCRETE	1.000	LS
631.1700	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	3,000.000	DL
633.1000	CPM SCHEDULE	12.000	EACH
635.1100	MOBILIZATION/DEMOBILIZATION	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE	1.000	LS
641.1500	PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH
646.2010	4 INCH WHITE LINE, WATERBORNE PAINT	2,200.000	LF
646.2111	4 INCH YELLOW LINE, WATERBORNE PAINT	2,200.000	LF
646.6000	TEMPORARY 4 INCH WHITE LINE	2,200.000	LF
646.6100	TEMPORARY 4 INCH YELLOW LINE	2,200.000	LF
649.1100	GEOTEXTILE FOR ROADBED SEPARATOR	2,740.000	SY
649.3100	GEOTEXTILE UNDER STONE FILL	1,030.000	SY
651.1500	TURF ESTABLISHMENT, GENERAL SEED	2,560.000	SY
651.1700	TURF ESTABLISHMENT, TEMPORARY SEED	2,500.000	SY
651.3500	TOPSOIL	285.000	CY
653.0100	EPSC PLAN	1.000	LS
653.0200	MONITORING EPSC PLAN	80.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	5,000.000	DL
653.1000	HAY MULCH	1.250	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	490.000	SY
653.2501	CHECK DAM, TYPE I	50.000	CY
653.3400	STABILIZED CONSTRUCTION ENTRANCE	2.000	EACH
653.4003	INLET PROTECTION DEVICE, TYPE III	15.000	CY
653.4701	SILT FENCE, TYPE I	1,000.000	LF
653.5000	BARRIER FENCE	770.000	LF
653.5500	PROJECT DEMARCATION FENCE	1,250.000	LF
653.6000	EROSION LOG	100.000	LF
675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	2.000	SF
675.3410	SQUARE TUBE SIGN POST AND ANCHOR	24.000	LF
676.1000	DELINEATOR WITH STEEL POST	3.000	EACH
690.0300	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	1.000	DL

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.