

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, November 06, 2026**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION: BEGINNING AT THE MONTPELIER / BERLIN TOWN LINE STA. B 0+51 (MM 0.010) AND PROGRESSING EAST ALONG US ROUTE 2 FOR A DISTANCE OF 4.598 MILES THROUGH THE TOWNS OF BERLIN AND BARRE TOWN AND INTO THE TOWN OF EAST MONTPELIER ENDING AT EAST MONTPELIER STA. E 165+75 (MM 3.139).

TYPE OF CONSTRUCTION: WORK TO BE PERFORMED UNDER THIS PROJECT INCLUDES COARSE-MILLING, RESURFACING WITH LEVELING AND WEARING COURSE, GUARDRAIL IMPROVEMENTS, DRAINAGE IMPROVEMENTS, SIGN REPLACEMENTS, PAVEMENT MARKINGS AND OTHER RELATED HIGHWAY ITEMS.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **October 15, 2027**.

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER's ESTIMATE: For this proposal the Engineer's Estimate is **Category E**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
<https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting>

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30 PM on Wednesday, October 28, 2026.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: <https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf>, and must be submitted/uploaded through the iCXWeb website at: <https://vtrans.exevision.com/icx/Index.aspx>

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
<https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications>

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at:
<https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding>

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
201.3100	THINNING AND TRIMMING FOR SIGNS	19.000	EACH
203.3000	EARTH BORROW	925.000	CY
203.4000	SHOULDER BERM REMOVAL	5,600.000	LF
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000	CY
210.1000	COARSE-MILLING, BITUMINOUS PAVEMENT	111,250.000	SY
213.3015	MILLED RUMBLE STRIPS, SINUSOIDAL CENTERLINE	14,900.000	LF
217.1000	REINFORCED SOIL SLOPE	290.000	SY
301.2600	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	775.000	CY
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	60.000	CY
402.1300	AGGREGATE SHOULDERS, RAP	740.000	TON
404.1100	TACK COAT, EMULSIFIED ASPHALT	1,175.000	CWT
406.0230	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III	710.000	TON
406.0310	BITUMINOUS CONCRETE PAVEMENT, TYPE IIIS, QA TIER I	11,500.000	TON
406.0410	BITUMINOUS CONCRETE PAVEMENT, TYPE IVS, QA TIER I	5,600.000	TON
406.2400	BITUMINOUS CONCRETE PAVEMENT, SURFACE PREPARATION, TYPE IVS	70.000	TON
406.3400	BITUMINOUS CONCRETE PAVEMENT, NON-PAVER PLACED, TYPE IVS	1,600.000	SY
406.9100	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	1.000	DL
406.9200	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	1.000	DL
406.9300	PAY ADJUSTMENT, BCP, LONGITUDINAL JOINT DENSITY (N.A.B.I.)	1.000	DL
406.9400	PAY ADJUSTMENT, BCP, PAVEMENT ROUGHNESS (N.A.B.I.)	1.000	DL
410.1000	MATERIAL TRANSFER VEHICLE	17,810.000	TON
516.1000	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	120.000	LF
524.2100	JOINT SEALER, POLYURETHANE	80.000	LF
604.4101	REHABILITATING DIS, CATCH BASINS, OR MANHOLES, CLASS I	21.000	EACH
604.4102	REHABILITATING DIS, CATCH BASINS, OR MANHOLES, CLASS II	3.000	EACH
604.4103	REHABILITATING DIS, CATCH BASINS, OR MANHOLES, CLASS III	3.000	EACH
604.6500	DECOMMISSION DROP INLET	3.000	EACH
608.1500	POWER GRADER RENTAL	40.000	HR
608.2501	ALL-PURPOSE EXCAVATOR RENTAL, TYPE I	240.000	HR
608.3001	POWER BROOM RENTAL, TYPE I	60.000	HR
608.3002	POWER BROOM RENTAL, TYPE II	110.000	HR
608.3700	TRUCK RENTAL	480.000	HR
608.4001	LOADER RENTAL, TYPE I	40.000	HR
613.1001	STONE FILL, TYPE I	1,400.000	CY
613.1002	STONE FILL, TYPE II	35.000	CY
616.3101	BITUMINOUS CONCRETE CURB, TYPE A	825.000	LF
616.4100	REMOVAL OF EXISTING CURB	830.000	LF
617.1100	REMOVE AND RESET MAILBOX, SINGLE SUPPORT	10.000	EACH
617.1200	REMOVE AND RESET MAILBOX, MULTIPLE SUPPORT	1.000	EACH
619.1700	YIELDING MARKER POSTS	90.000	EACH
621.0100	REMOVAL OF GUARDRAIL	7,750.000	LF
621.0300	REPLACE GUARDRAIL BEAM UNIT, W-BEAM	110.000	EACH
621.0360	REPLACE GUARDRAIL POST ASSEMBLY, W-BEAM WITH 6 FOOT POSTS	85.000	EACH
621.0450	REPLACE GUARDRAIL POST ASSEMBLY, BOX BEAM	2.000	EACH
621.1060	STEEL BEAM GUARDRAIL	6,275.000	LF
621.1080	STEEL BEAM GUARDRAIL WITH 8 FOOT POSTS	75.000	LF
621.1500	STEEL BEAM GUARDRAIL OFFSET BLOCK	85.000	EACH

621.1560	TRAFFIC BARRIER DELINEATOR	225.000	EACH
621.3130	MTS, MGS, FLARED, TL-3	35.000	EACH
621.4130	MTS, BOX BEAM, FLARED, TL-3	2.000	EACH
625.6002	WIRED CONDUIT, 2 INCH	30.000	LF
630.1000	UNIFORMED TRAFFIC OFFICERS	900.000	HR
630.1500	FLAGGERS	3,000.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1700	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	3,000.000	DL
633.1000	CPM SCHEDULE	5.000	EACH
634.1000	EMPLOYEE TRAINEESHIP	520.000	HR
635.1100	MOBILIZATION/DEMOBILIZATION	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE	1.000	LS
641.1500	PORTABLE CHANGEABLE MESSAGE SIGN	4.000	EACH
646.6020	TEMPORARY 4 INCH WHITE LINE, PAINT	98,400.000	LF
646.6120	TEMPORARY 4 INCH YELLOW LINE, PAINT	94,000.000	LF
646.6220	TEMPORARY 6 INCH WHITE LINE, PAINT	200.000	LF
646.6520	TEMPORARY 8 INCH YELLOW LINE, PAINT	1,300.000	LF
646.6820	TEMPORARY 24 INCH STOP BAR, PAINT	390.000	LF
646.6920	TEMPORARY LETTER OR SYMBOL, PAINT	72.000	EACH
646.7020	TEMPORARY CROSSWALK MARKING, PAINT	460.000	LF
646.7600	LINE STRIPING TARGETS	9,900.000	EACH
651.1500	TURF ESTABLISHMENT, GENERAL SEED	5,080.000	SY
651.3500	TOPSOIL	90.000	CY
651.4006	GRUBBING MATERIAL, 6 INCH	1,200.000	SY
653.1000	HAY MULCH	2.000	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	2,520.000	SY
675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	250.000	SF
675.3410	SQUARE TUBE SIGN POST AND ANCHOR	675.000	LF
675.5000	SIGN REMOVAL, FLAT SHEET ALUMINUM	45.000	EACH
675.6000	RESETTING SIGNS	3.000	EACH
676.1000	DELINEATOR WITH STEEL POST	43.000	EACH
676.1200	REMOVAL OF EXISTING DELINEATOR AND POST	43.000	EACH
678.2005	CABINET ASSEMBLY	1.000	EACH
678.2040	VEHICLE DETECTION SYSTEM	1.000	EACH
678.2045	PAN-TILT-ZOOM CAMERA	1.000	EACH
679.4600	STREET LIGHT ASSEMBLY (25FT POLE)	1.000	EACH
679.4600	STREET LIGHT ASSEMBLY (30FT POLE)	2.000	EACH
679.4700	BRACKET ARM	3.000	EACH
679.5000	LUMINAIRE	3.000	EACH
690.0300	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	1.000	DL
690.0400	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	1.000	DL
OPTION - PAVEMENT MARKING OPTIONS LINES - EPOXY PAINT LINES ITEMS			
646.4030	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	49,200.000	LF
646.4130	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	47,000.000	LF
646.4230	DURABLE 6 INCH WHITE LINE, EPOXY PAINT	100.000	LF
646.4530	DURABLE 8 INCH YELLOW LINE, EPOXY PAINT	650.000	LF
OPTION - PAVEMENT MARKING OPTIONS LINES - POLYUREA PAINT LINES ITEMS			
646.4040	DURABLE 4 INCH WHITE LINE, POLYUREA	49,200.000	LF
646.4140	DURABLE 4 INCH YELLOW LINE, POLYUREA	47,000.000	LF
646.4240	DURABLE 6 INCH WHITE LINE, POLYUREA	100.000	LF
646.4540	DURABLE 8 INCH YELLOW LINE, POLYUREA	650.000	LF
OPTION - PAVEMENT MARKING OPTIONS STOP BAR - EPOXY PAINT STOP BAR ITEMS			
646.4830	DURABLE 24 INCH STOP BAR, EPOXY PAINT	195.000	LF
OPTION - PAVEMENT MARKING OPTIONS STOP BAR - POLYUREA PAINT STOP BAR ITEMS			
646.4840	DURABLE 24 INCH STOP BAR, POLYUREA	195.000	LF
OPTION - PAVEMENT MARKING OPTIONS SYMBOLS - EPOXY PAINT LETTERS AND SYMBOLS ITEMS			

646.4930	DURABLE LETTER OR SYMBOL, EPOXY PAINT	36.000	EACH
OPTION - PAVEMENT MARKING OPTIONS SYMBOLS - POLYUREA PAINT LETTERS AND SYMBOLS ITEMS			
646.4940	DURABLE LETTER OR SYMBOL, POLYUREA	36.000	EACH
OPTION - PAVEMENT MARKING OPTIONS XWALK - EPOXY PAINT CROSSWALK ITEMS			
646.5030	DURABLE CROSSWALK MARKING, EPOXY PAINT	230.000	LF
OPTION - PAVEMENT MARKING OPTIONS XWALK - POLYUREA PAINT CROSSWALK ITEMS			
646.5040	DURABLE CROSSWALK MARKING, POLYUREA	230.000	LF

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.