

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, November 13, 2026**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION:

PLYMOUTH ER P23-1(327) - IN THE TOWN OF PLYMOUTH ON VT ROUTE 100A APPROXIMATELY 4.62 MILES SOUTH OF THE INTERSECTION WITH US ROUTE 4.

PLYMOUTH ER P23-1(328) - IN THE TOWN OF PLYMOUTH ON VT ROUTE 100A APPROXIMATELY 3.71 MILES SOUTH OF THE INTERSECTION WITH US ROUTE 4.

TYPE OF CONSTRUCTION:

PLYMOUTH ER P23-1(327) - Replacement of Bridge 4 over Pinney Hollow Brook with approach roadway and related channel work.

PLYMOUTH ER P23-1(328) - Replacement of Bridge 7 over Pinney Hollow Brook with approach roadway and related channel work.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **October 15, 2028**.

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER's ESTIMATE: For this proposal the Engineer's Estimate is **Category F**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
<https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting>

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30 PM on Wednesday, November 4, 2026.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: <https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf>, and must be submitted/uploaded through the iCXWeb website at: <https://vtrans.exevision.com/icx/Index.aspx>

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
<https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications>

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any

contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at: <https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding>

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
199.8101	INCENTIVE OR DISINCENTIVE (N.A.B.I.) (BRIDGE 4)	136,080.00 0	DL
199.8101	INCENTIVE OR DISINCENTIVE (N.A.B.I.) (BRIDGE 7)	131,000.00 0	DL
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (BRIDGE 4)	1.000	LS
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (BRIDGE 7)	1.000	LS
203.1500	COMMON EXCAVATION	1,890.000	CY
203.1600	SOLID ROCK EXCAVATION	57.000	CY
203.2700	UNCLASSIFIED CHANNEL EXCAVATION	1,320.000	CY
203.3000	EARTH BORROW	105.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	2.000	CY
204.2500	STRUCTURE EXCAVATION	1,350.000	CY
204.3000	GRANULAR BACKFILL FOR STRUCTURES	450.000	CY
210.1000	COARSE-MILLING, BITUMINOUS PAVEMENT	325.000	SY
225.0500	RETAINING WALL, CONCRETE (BRIDGE 7)	1.000	LS
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	1,500.000	CY
401.1000	AGGREGATE SURFACE COURSE	58.000	CY
404.1100	TACK COAT, EMULSIFIED ASPHALT	20.000	CWT
406.0230	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III	264.000	TON
406.1430	BITUMINOUS CONCRETE PAVEMENT, TYPE IVSB, QA TIER III	420.000	TON
406.3400	BITUMINOUS CONCRETE PAVEMENT, NON-PAVER PLACED, TYPE IVS	182.000	SY
406.9100	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	2.000	DL
406.9200	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	2.000	DL
501.3700	PERFORMANCE-BASED CONCRETE, CLASS PCD	13.000	CY
501.3800	PERFORMANCE-BASED CONCRETE, CLASS PCS	115.000	CY
504.1000	FURNISHING EQUIPMENT FOR DRIVING PILING (BRIDGE 7)	1.000	LS
505.2000	STEEL PILING, HP 14 × 117 (BRIDGE 7)	600.000	LF
505.4500	DYNAMIC PILE LOADING TEST	2.000	EACH
507.1100	REINFORCING STEEL, LEVEL I	13,015.000	LB
507.1200	REINFORCING STEEL, LEVEL II	3,935.000	LB
510.2500	PRESTRESSED CONCRETE SOLID SLABS (SDB40-18, BRIDGE 4)	305.000	LF
510.2500	PRESTRESSED CONCRETE SOLID SLABS (SDB40-21, BRIDGE 7)	395.000	LF
514.1000	WATER REPELLENT, SILANE	3.000	GAL
519.1000	MEMBRANE WATERPROOFING, SPRAY APPLIED	340.000	SY
524.1100	JOINT SEALER, HOT POURED	315.000	LF
525.3130	BRIDGE RAILING, GALVANIZED 3 RAIL BOX BEAM	210.000	LF
529.1500	REMOVAL OF STRUCTURE (BRIDGE 4, 1,181 SF - EST)	1.000	EACH
529.1500	REMOVAL OF STRUCTURE (BRIDGE 7, 1,099 SF - EST)	1.000	EACH

531.1700	BEARING DEVICE ASSEMBLY, STEEL REINFORCED ELASTOMERIC PAD	42.000	EACH
540.1000	PRECAST CONCRETE STRUCTURE (ABUTMENT 1 - BRIDGE 4)	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (ABUTMENT 1 - BRIDGE 7)	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (ABUTMENT 2 - BRIDGE 4)	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (ABUTMENT 2 - BRIDGE 7)	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (APPROACH SLAB 2 - BRIDGE 4)	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (APPROACH SLAB 1 - BRIDGE 4)	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (APPROACH SLAB 1 - BRIDGE 7)	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (APPROACH SLAB 2 - BRIDGE 7)	1.000	LS
541.4500	FLOWABLE FILL	35.000	CY
542.1000	HIGH PERFORMANCE CONCRETE, RAPID SET	104.000	CY
547.1000	MICROPILE, CASED	573.000	LF
547.1500	MICROPILE, UNCASED	224.000	LF
547.2000	MICROPILE OBSTRUCTION DRILLING AND REMOVAL	160.000	LF
547.2500	FURNISHING EQUIPMENT FOR INSTALLING MICROPILES (BRIDGE 4)	1.000	LS
604.4000	CHANGING ELEVATION OF DIS, CATCH BASINS, OR MANHOLES	1.000	EACH
609.1000	DUST CONTROL WITH WATER	108.000	MGAL
613.0602	E-STONE FILL, TYPE II	480.000	CY
613.0604	E-STONE FILL, TYPE IV	425.000	CY
614.2000	IN-WATER SEDIMENT ISOLATION MEASURES (BRIDGE 4)	1.000	LS
614.2000	IN-WATER SEDIMENT ISOLATION MEASURES (BRIDGE 7)	1.000	LS
616.2502	PRECAST REINFORCED CONCRETE CURB, TYPE B	170.000	LF
617.1100	REMOVE AND RESET MAILBOX, SINGLE SUPPORT	4.000	EACH
619.1700	YIELDING MARKER POSTS	1.000	EACH
621.0100	REMOVAL OF GUARDRAIL	442.000	LF
621.1060	STEEL BEAM GUARDRAIL	258.000	LF
621.1530	ANCHOR FOR STEEL BEAM GUARDRAIL, MGS	4.000	EACH
621.2400	TEMPORARY TRAFFIC BARRIER	63.000	LF
621.8130	GUARDRAIL APPROACH SECTION, 3 RAIL BOX BEAM	8.000	EACH
630.1000	UNIFORMED TRAFFIC OFFICERS	504.000	HR
630.1500	FLAGGERS	1,008.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1600	TESTING EQUIPMENT, CONCRETE	1.000	LS
631.1700	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.1900	TESTING EQUIPMENT, GROUT	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	6,000.000	DL
633.1000	CPM SCHEDULE	8.000	EACH
635.1100	MOBILIZATION/DEMOBILIZATION (BRIDGE 4)	1.000	LS
635.1100	MOBILIZATION/DEMOBILIZATION (BRIDGE 7)	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE (BRIDGE 4)	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE (BRIDGE 7)	1.000	LS
641.1500	PORTABLE CHANGEABLE MESSAGE SIGN	6.000	EACH
646.4040	DURABLE 4 INCH WHITE LINE, POLYUREA	1,575.000	LF
646.4140	DURABLE 4 INCH YELLOW LINE, POLYUREA	1,575.000	LF
646.6020	TEMPORARY 4 INCH WHITE LINE, PAINT	3,150.000	LF
646.6120	TEMPORARY 4 INCH YELLOW LINE, PAINT	3,150.000	LF
646.7600	LINE STRIPING TARGETS	320.000	EACH
649.1100	GEOTEXTILE FOR ROADBED SEPARATOR	2,080.000	SY
651.1500	TURF ESTABLISHMENT, GENERAL SEED	2,420.000	SY
651.3500	TOPSOIL	270.000	CY
651.4012	GRUBBING MATERIAL, 12 INCH	310.000	SY
653.0100	EPSC PLAN (BRIDGE 4)	1.000	LS
653.0100	EPSC PLAN (BRIDGE 7)	1.000	LS
653.0200	MONITORING EPSC PLAN	50.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	4,000.000	DL
653.1000	HAY MULCH	8.500	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	2,420.000	SY

653.3400	STABILIZED CONSTRUCTION ENTRANCE	4.000	EACH
653.4001	INLET PROTECTION DEVICE, TYPE I	1.000	EACH
653.4003	INLET PROTECTION DEVICE, TYPE III	1.000	CY
653.4702	SILT FENCE, TYPE II	950.000	LF
653.5000	BARRIER FENCE	450.000	LF
653.5500	PROJECT DEMARCATION FENCE	935.000	LF
656.8500	TREE PROTECTION (BRIDGE 7)	1.000	LS
675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	2.000	SF
675.3410	SQUARE TUBE SIGN POST AND ANCHOR	40.000	LF
675.5000	SIGN REMOVAL, FLAT SHEET ALUMINUM	4.000	EACH
676.1000	DELINEATOR WITH STEEL POST	7.000	EACH
690.0300	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	2.000	DL

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.