Table of Contents _____ 1
p21v228_21v219 Addendum 1 Letter _____ 2
p21v228_21v219 Plan Sheets _____ 3

State of Vermont
Contract Administration
Barre City Place
219 North Main Street, Suite 105
Barre VT 05641
http://vtrans.vermont.gov

Agency of Transportation
Finance & Administration
[phone] 802-622-1285
[ttd] 800-253-0191

November 2, 2026

C03156 – Northfield-Williamstown STP SURF(76), Randolph STP SURF(78)

ADDENDUM #1

Bidders:

Changes have been made to the documents located on the Bid Opportunity website as noted below:

REVISED: Plan sheets 2 and 12

ADDED: None.

DELETED: None.

INDEX OF SHEETS

COMPOSITE PROJECT SHEETS

1	COMPOSITE TITLE SHEET
2	COMPOSITE INDEX OF SHEETS
3	CONVENTIONAL SYMBOLOGY - LEGEND SHEET
4	COMPOSITE PROJECT NOTES SHEET
5	COMPOSITE DETAIL SHEET
6-7	COMPOSITE PAVEMENT MARKING DETAIL SHEETS

NORTHFIELD-WILLIAMSTOWN

8	TITLE SHEET
9-10	TYPICAL SHEETS
11	DETAIL SHEET
12-13	QUANTITY SHEETS
14-26	PLAN SHEETS
27-28	CONSTRUCTION APPROACH SIGNING SHEET
29-31	ROUGH AND RUT DATA SHEETS

RANDOLPH

32	TITLE SHEET
33-34	TYPICAL SHEETS
35	DETAIL SHEET
36-37	QUANTITY SHEETS
38	BRIDGE DETAIL SHEET
39-74	PLAN SHEETS
75-76	CONSTRUCTION APPROACH SIGNING SHEET
77-78	ROUGH AND RUT DATA SHEETS

VTRANS STANDARDS

S-400	04/07/20	BRIDGE JOINT ASPHALTIC PLUG
T-1	06/24/25	TRAFFIC CONTROL GENERAL NOTES
T-10	06/24/25	CONVENTIONAL ROADS CONSTRUCTION APPROACH SIGNING
T-17	06/24/25	TRAFFIC CONTROL MISCELLANEOUS DETAILS
T-24	06/24/25	TRAFFIC CONTROL FOR MAINTENANCE PAVEMENT MARKING OPERATION
T-28	06/24/25	CONSTRUCTION SIGN DETAILS
T-29	06/24/25	CONSTRUCTION SIGN DETAILS
T-30	02/17/22	CONSTRUCTION SIGN DETAILS
T-31	06/24/25	CONSTRUCTION SIGN DETAILS
T-35	06/24/25	CONSTRUCTION ZONE LONGITUDINAL DROP-OFFS
T-36	06/24/25	CONSTRUCTION ZONE LONGITUDINAL DROP-OFFS FOR PAVING
T-40	06/24/25	DELINEATORS AND MILE POSTS
T-45	06/24/25	SQUARE TUBE SIGN POST AND ANCHOR
T-56	06/24/25	STANDARD SIGN PLACEMENT
T-180	07/22/26	MILLED RUMBLE STRIPS (SINUSOIDAL CENTERLINE)
T-191	06/24/25	PAVEMENT MARKING DETAILS
T-193	06/24/25	PAVEMENT MARKING DETAILS

HIGHWAY SAFETY & DESIGN DETAILS

HSD-621.06	02-27-17	MISCELLANEOUS GUARDRAIL DETAILS

TRAFFIC DATA NORTHFIELD-WILLIAMSTOWN

VT ROUTE 64	AADT		DHV		%T			%D			ESAL'S	
	2026	2036	2026	2036	2026		2036	2026		2036	2026-2036	2026-2046
BEGIN PROJECT TO I-89 EXIT 5 RAMPS C/D	5000	5200	670	700	~~5000~~ 60		~~5200~~ 60	~~670~~ 7.9		~~700~~ 9.7	737,000	1,659,000
EXIT 5 RAMPS C/D TO EXIT 5 RAMPS A/B	4400	4600	500	530	~~4400~~ 72		~~4600~~ 72	~~500~~ 3.9		~~530~~ 4.9	1,014,000	2,480,000
EXIT 5 RAMPS A/B TO END PROJECT	2800	2900	310	330	~~2800~~ 64		~~2900~~ 64	~~310~~ 4.2		~~330~~ 5.2	751,000	1,822,000

TRAFFIC DATA RANDOLPH

VT ROUTE 66	AADT		DHV		%T		%D		ESAL'S	
	2026	2036	2026	2036	2026	2036	2026	2036	2026-2036	2026-2046
BEGIN PROJECT TO I-89 EXIT 4 RAMPS A/C (MM 2.435)	6200	6500	780	820	8.1	9.8	53	53	1,706,000	2,422,000
I-89 EXIT 4 RAMPS A\C TO I-89 EXIT 4 RAMPS B/D (MM 2.607)	6500	6800	730	750	3.6	4.6	53	53	1,224,000	3,018,000
I-89 EXIT 4 RAMPS B/D TO EAST BETHEL RD (MM 3.342)	4900	5100	560	590	3.9	5.0	52	52	951,000	2,339,000
EAST BETHEL RD TO RIDGE RD (MM 3.896)	2600	2700	300	310	5.5	6.6	65	65	563,000	1,249,000
RIDGE ROAD TO END PROJECT	1100	1100	150	150	12.9	15.2	55	55	248,000	543,000

SUPERPAVE BITUMINOUS CONCRETE PAVEMENT MIXTURE DESIGN CRITERIA ~~VT 66~~ VT 64 & VT 66

DESIGN LANE/DESIGN LIFE ESALS	~~298,650~~ 1,599,540
DESIGN NUMBER OF GYRATIONS	65
PERFORMANCE GRADE ASPHALT BINDER - PAVER PLACED	TYPE III S 58E-28
PERFORMANCE GRADE ASPHALT BINDER - NON-PAVER PLACED	~~58S-28~~ 58S-34

ADDENDUM	REVISION	PLOT DATE	DESCRIPTION	BY
1	1	11/2/2026	UPDATED TRAFFIC DATA	NP
1	1	11/2/2026	UPDATED VT ROUTES	NP
1	1	11/2/2026	UPDATED DESIGN LANE/ DESIGN LIFE ESALS	NP
1	1	11/2/2026	UPDATED ASPHALT BINDER - NON-PAVER PLACED	NP

PROJECT NAME: NORTHFIELD-WILLIAMSTOWN & RANDOLPH

PROJECT NUMBER: STP SURF(76) & STP SURF(78)

FILE NAME: p21v228 N-W.dgn
PROJECT LEADER: B. KIPP
DESIGNED BY: N. PAPPAS
COMPOSITE INDEX OF SHEETS

PLOT DATE: 2-NOV-2026
DRAWN BY: N. PAPPAS
CHECKED BY: B. KIPP
SHEET 2 OF 78

STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES				TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
1011 - ROADWAY	1031 - TRAINING	1999 - FULL C.E. ITEMS	OPTION	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
10575				10575		LF	SHOULDER BERM REMOVAL	203.4000	EST.			
1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.2200	-			FINE-MILLING, BITUMINOUS PAVEMENT
86300				86300		SY	FINE-MILLING, BITUMINOUS PAVEMENT	210.1200	228	86072	SY	MAINLINE
12200				12200		LF	MILLED RUMBLE STRIPS, SINUSOIDAL CENTERLINE	213.3015	125	228	SY	ROUNDING
550				550		TON	AGGREGATE SHOULDERS, RAP	402.1300	27	86300	SY	TOTAL
600				600		CWT	TACK COAT, EMULSIFIED ASPHALT	404.1100	28			TACK COAT, EMULSIFIED ASHPALT
35				35		CWT	FOG SEAL, EMULSIFIED ASPHALT	404.3100	1	572	CWT	MAINLINE
5100				5100		TON	BITUMINOUS CONCRETE PAVEMENT, THIN OVERLAY	406.0410002	79	28	CWT	ROUNDING
150				150		TON	BITUMINOUS CONCRETE PAVEMENT, SURFACE PREPARATION, TYPE IVS	406.2400	EST.	600	CWT	TOTAL
1				1		DL	PAY ADJUSTMENT, BCP, TO, MIXTURE PROPERTIES (N.A.B.I.)	406.9100003	-			BITUMINOUS CONCRETE PAVEMENT, TYPE IVS, QA TIER I
5100				5100		TON	MATERIAL TRANSFER VEHICLE	410.1000	79	5021	TON	MAINLINE
7800				7800		LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (ASTM D 6690 TYPE II)	417.2000	EST.	79	TON	ROUNDING
50				50		HR	ALL-PURPOSE EXCAVATOR RENTAL, TYPE I	608.2501	EST.	5100	TON	TOTAL
25				25		HR	POWER BROOM RENTAL, TYPE I	608.3001	EST.			MATERIAL TRANSFER VEHICLE
40				40		HR	POWER BROOM RENTAL, TYPE II	608.3002	EST.	5021	TON	MAINLINE
100				100		HR	TRUCK RENTAL	608.3700	EST.	79	TON	ROUNDING
15				15		HR	LOADER RENTAL, TYPE I	608.4001	EST.	5100	TON	TOTAL
200				200		EACH	TRAFFIC BARRIER DELINEATOR	621.1560	EST.			
1500				1500		HR	UNIFORMED TRAFFIC OFFICERS	630.1000	EST.			
1260				1260		HR	FLAGGERS	630.1500	EST.			
		0.3		0.3		LS	FIELD OFFICE, ENGINEER'S	631.1000	EST.			
		0.3		0.3		LS	TESTING EQUIPMENT, BITUMINOUS	631.1700	-			
		1500		1500		DL	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	631.2600	-			
	160			160		HR	EMPLOYEE TRAINEESHIP	634.1000	-			
1				1		LS	MOBILIZATION/DEMOBILIZATION (STP SURF(76))	635.1100	-			
1				1		LS	TRAFFIC CONTROL, ALL-INCLUSIVE (STP SURF(76))	641.1100	-			
6				6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.1500	-			
75500				75500		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.6020	213			
63110				63110		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.6120	317			
450				450		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.6820	10			
130				130		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.6920	-			
6800				6800		EACH	LINE STRIPING TARGETS	646.7600	EST.			
10				10		EACH	DELINEATOR WITH STEEL POST	676.1000	10			
10				10		EACH	REMOVAL OF EXISTING DELINEATOR AND POST	676.1200	10			
1				1		DL	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	690.0300	-			
1				1		DL	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.0400	-			
							BEGIN OPTION EPOXY PAINT ITEMS					
			37900	37900		LF	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	646.4030	313			
			31750	31750		LF	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	646.4130	317			
			80	80		LF	DURABLE 8 INCH YELLOW LINE, EPOXY PAINT	646.4530	EST.			

ADDENDUM	REVISION	PLOT DATE	DESCRIPTION	BY
△	1	11/2/2026	UPDATED COLUMMN WIDTH	NP

PROJECT NAME: NORTHFIELD-WILLIAMSTOWN
PROJECT NUMBER: STP SURF(76)

FILE NAME: p21v228 N-W.dgn
PROJECT LEADER: B. KIPP
DESIGNED BY: N. PAPPAS
QUANTITY SHEET 1

PLOT DATE: 2-NOV-2026
DRAWN BY: N. PAPPAS
CHECKED BY: B. KIPP
SHEET 12 OF 78