VERMONT AGENCY OF TRANSPORTATION MONTPELIER, VERMONT

Brookfield ER P23-1(668) **November 04, 2026**

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, December 04, 2026**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION: 250 FEET NORTH OF THE INTERSECTION OF VT ROUTE 65 AND SUNSET LANE.

TYPE OF CONSTRUCTION: WORK TO BE PERFORMED UNDER THIS PROJECT INCLUDES REPLACEMENT OF TWO EXISTING CORRUGATED METAL PIPES WITH A NEW STRUCTURE, ADJACENT ROADWAY APPROACHES AND CHANNEL WORK.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **October 01, 2027.**

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER's ESTIMATE: For this proposal the Engineer's Estimate is **Category D**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30 PM on Wednesday, November 18, 2026.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf, and must be submitted/uploaded through the iCXWeb website at: https://vtrans.exevision.com/icx/Index.aspx

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at: https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
199.8101	INCENTIVE OR DISINCENTIVE (N.A.B.I.)	58,500.000	DL
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	1.000	LS
203.1500	COMMON EXCAVATION	275.000	CY
203.1600	SOLID ROCK EXCAVATION	20.000	CY
203.2700	UNCLASSIFIED CHANNEL EXCAVATION	150.000	CY
204.2000	TRENCH EXCAVATION OF EARTH	110.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000	CY
204.2500	STRUCTURE EXCAVATION	800.000	CY
204.3000	GRANULAR BACKFILL FOR STRUCTURES	250.000	CY
250.0100	CONSTRUCTION VIBRATION AND CRACK MONITORING	1.000	LS
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	175.000	CY
401.1000	AGGREGATE SURFACE COURSE	110.000	CY
501.3800	PERFORMANCE-BASED CONCRETE, CLASS PCS	20.000	CY
507.1200	REINFORCING STEEL, LEVEL II	900.000	LB
507.1600	DRILLING AND GROUTING DOWELS	120.000	LF
514.1000	WATER REPELLENT, SILANE	2.000	GAL
527.1000002	LOCAL ROADWAY MAINTENANCE (N.A.B.I.)	40,000.000	DL
529.1500	REMOVAL OF STRUCTURE (TWO CMP, 640 SF-EST)	1.000	EACH
540.1000	PRECAST CONCRETE STRUCTURE (15’-0” X 7’-0” X 75’-0” BOX CULVERT)	1.000	LS
601.0915	18 INCH CPEP	70.000	LF
601.7015	18 INCH CPEPES	1.000	EACH
604.4103	REHABILITATING DIS, CATCH BASINS, OR MANHOLES, CLASS III	1.000	EACH
608.2501	ALL-PURPOSE EXCAVATOR RENTAL, TYPE I	10.000	HR
613.0601	E-STONE FILL, TYPE I	60.000	CY
613.0602	E-STONE FILL, TYPE II	120.000	CY
614.1000	TEMPORARY RELOCATION OF STREAM	1.000	EACH
617.1100	REMOVE AND RESET MAILBOX, SINGLE SUPPORT	1.000	EACH
630.1000	UNIFORMED TRAFFIC OFFICERS	160.000	HR
630.1500	FLAGGERS	240.000	HR
631.1000	FIELD OFFICE, ENGINEER’S	1.000	LS
631.1600	TESTING EQUIPMENT, CONCRETE	1.000	LS
631.1900	TESTING EQUIPMENT, GROUT	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	3,000.000	DL
633.1000	CPM SCHEDULE	4.000	EACH
634.1000	EMPLOYEE TRAINEESHIP	520.000	HR
635.1100	MOBILIZATION/DEMOBILIZATION	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE	1.000	LS
641.1500	PORTABLE CHANGEABLE MESSAGE SIGN	4.000	EACH
649.1100	GEOTEXTILE FOR ROADBED SEPARATOR	525.000	SY
649.3100	GEOTEXTILE UNDER STONE FILL	50.000	SY
651.1500	TURF ESTABLISHMENT, GENERAL SEED	1,050.000	SY
651.3500	TOPSOIL	120.000	CY
651.4012	GRUBBING MATERIAL, 12 INCH	30.000	SY
653.0100	EPSC PLAN	1.000	LS
653.0200	MONITORING EPSC PLAN	50.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	4,300.000	DL

653.1000	HAY MULCH	1.000	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	1,100.000	SY
653.3400	STABILIZED CONSTRUCTION ENTRANCE	40.000	EACH
653.4001	INLET PROTECTION DEVICE, TYPE I	1.000	EACH
653.4500	FILTER BAG	1.000	EACH
653.4701	SILT FENCE, TYPE I	220.000	LF
653.5000	BARRIER FENCE	550.000	LF
675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	1.000	SF
675.3410	SQUARE TUBE SIGN POST AND ANCHOR	16.000	LF
675.5000	SIGN REMOVAL, FLAT SHEET ALUMINUM	1.000	EACH
675.6000	RESETTING SIGNS	1.000	EACH
676.1000	DELINEATOR WITH STEEL POST	1.000	EACH

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.