Table of Contents _____ 1
p21v228_21v219 Letter _____ 2
p21v228_21v219 Plans _____ 3

State of Vermont
Contract Administration
Barre City Place
219 North Main Street, Suite 105
Barre VT 05641
http://vtrans.vermont.gov

Agency of Transportation
Finance & Administration
[phone] 802-622-1285
[ttd] 800-253-0191

November 4, 2026

C03156 – Northfield-Williamstown STP SURF(76), Randolph STP SURF(78)

ADDENDUM #2

Bidders:

Changes have been made to the documents located on the Bid Opportunity website as noted below:

REVISED: Plan sheet 2.

ADDED: None.

DELETED: None.

VTrans Mission and Vision

Through excellent customer service, provide for the safe and efficient movement of people and goods.
A safe, reliable, and multimodal transportation system that grows the economy, is affordable to use and operate, and serves vulnerable populations.

INDEX OF SHEETS

COMPOSITE PROJECT SHEETS

1	COMPOSITE TITLE SHEET
2	COMPOSITE INDEX OF SHEETS
3	CONVENTIONAL SYMBOLOGY - LEGEND SHEET
4	COMPOSITE PROJECT NOTES SHEET
5	COMPOSITE DETAIL SHEET
6-7	COMPOSITE PAVEMENT MARKING DETAIL SHEETS

NORTHFIELD-WILLIAMSTOWN

8	TITLE SHEET
9-10	TYPICAL SHEETS
11	DETAIL SHEET
12-13	QUANTITY SHEETS
14-26	PLAN SHEETS
27-28	CONSTRUCTION APPROACH SIGNING SHEET
29-31	ROUGH AND RUT DATA SHEETS

RANDOLPH

32	TITLE SHEET
33-34	TYPICAL SHEETS
35	DETAIL SHEET
36-37	QUANTITY SHEETS
38	BRIDGE DETAIL SHEET
39-74	PLAN SHEETS
75-76	CONSTRUCTION APPROACH SIGNING SHEET
77-78	ROUGH AND RUT DATA SHEETS

VTRANS STANDARDS

S-400	04/07/20	BRIDGE JOINT ASPHALTIC PLUG
T-1	06/24/25	TRAFFIC CONTROL GENERAL NOTES
T-10	06/24/25	CONVENTIONAL ROADS CONSTRUCTION APPROACH SIGNING
T-17	06/24/25	TRAFFIC CONTROL MISCELLANEOUS DETAILS
T-24	06/24/25	TRAFFIC CONTROL FOR MAINTENANCE PAVEMENT MARKING OPERATION
T-28	06/24/25	CONSTRUCTION SIGN DETAILS
T-29	06/24/25	CONSTRUCTION SIGN DETAILS
T-30	02/17/22	CONSTRUCTION SIGN DETAILS
T-31	06/24/25	CONSTRUCTION SIGN DETAILS
T-35	06/24/25	CONSTRUCTION ZONE LONGITUDINAL DROP-OFFS
T-36	06/24/25	CONSTRUCTION ZONE LONGITUDINAL DROP-OFFS FOR PAVING
T-40	06/24/25	DELINEATORS AND MILE POSTS
T-45	06/24/25	SQUARE TUBE SIGN POST AND ANCHOR
T-56	06/24/25	STANDARD SIGN PLACEMENT
T-180	07/22/26	MILLED RUMBLE STRIPS (SINUSOIDAL CENTERLINE)
T-191	06/24/25	PAVEMENT MARKING DETAILS
T-193	06/24/25	PAVEMENT MARKING DETAILS

HIGHWAY SAFETY & DESIGN DETAILS

HSD-621.06	02-27-17	MISCELLANEOUS GUARDRAIL DETAILS

TRAFFIC DATA NORTHFIELD-WILLIAMSTOWN

VT ROUTE 64	AADT		DHV		%T		%D		ESAL'S	
	2026	2036	2026	2036	2026	2036	2026	2036	2026-2036	2026-2046
BEGIN PROJECT TO I-89 EXIT 5 RAMPS C/D	5000	5200	670	700	~~5000~~ 60	~~5200~~ 60	~~670~~ 7.9	~~700~~ 9.7	737,000	1,659,000
EXIT 5 RAMPS C/D TO EXIT 5 RAMPS A/B	4400	4600	500	530	~~4400~~ 72	~~4600~~ 72	~~500~~ 3.9	~~530~~ 4.9	1,014,000	2,480,000
EXIT 5 RAMPS A/B TO END PROJECT	2800	2900	310	330	~~2800~~ 64	~~2900~~ 64	~~310~~ 4.2	~~330~~ 5.2	751,000	1,822,000

△1

TRAFFIC DATA RANDOLPH

VT ROUTE 66	AADT		DHV		%T		%D		ESAL'S	
	2026	2036	2026	2036	2026	2036	2026	2036	2026-2036	2026-2046
BEGIN PROJECT TO I-89 EXIT 4 RAMPS A/C (MM 2.435)	6200	6500	780	820	8.1	9.8	53	53	1,706,000	2,422,000
I-89 EXIT 4 RAMPS A\C TO I-89 EXIT 4 RAMPS B/D (MM 2.607)	6500	6800	730	750	3.6	4.6	53	53	1,224,000	3,018,000
I-89 EXIT 4 RAMPS B/D TO EAST BETHEL RD (MM 3.342)	4900	5100	560	590	3.9	5.0	52	52	951,000	2,339,000
EAST BETHEL RD TO RIDGE RD (MM 3.896)	2600	2700	300	310	5.5	6.6	65	65	563,000	1,249,000
RIDGE ROAD TO END PROJECT	1100	1100	150	150	12.9	15.2	55	55	248,000	543,000

SUPERPAVE BITUMINOUS CONCRETE PAVEMENT MIXTURE DESIGN CRITERIA ~~VT 66~~ VT 64 & VT 66 △1	
DESIGN LANE/DESIGN LIFE ESALS	△1 ~~298,650~~ 1,599,540
DESIGN NUMBER OF GYRATIONS	65 TYPE III S
PERFORMANCE GRADE ASPHALT BINDER - PAVER PLACED	△2 ~~58E-28~~ 58E-34
PERFORMANCE GRADE ASPHALT BINDER - NON-PAVER PLACED	△1 ~~58S-28~~ 58S-34

ADDENDUM	REVISION	PLOT DATE	DESCRIPTION	BY
△1	1	11/2/2026	UPDATED TRAFFIC DATA	NP
△1	1	11/2/2026	UPDATED VT ROUTES	NP
△1	1	11/2/2026	UPDATED DESIGN LANE/ DESIGN LIFE ESALS	NP
△1	1	11/2/2026	UPDATED ASPHALT BINDER - NON-PAVER PLACED	NP
△2	2	11/4/2026	UPDATED ASPHALT BINDER - PAVER PLACED	NP

PROJECT NAME: NORTHFIELD-WILLIAMSTOWN & RANDOLPH

PROJECT NUMBER: STP SURF(76) & STP SURF(78)

FILE NAME: p21v228 N-W.dgn
PROJECT LEADER: B. KIPP
DESIGNED BY: N. PAPPAS
COMPOSITE INDEX OF SHEETS

PLOT DATE: 4-NOV-2026
DRAWN BY: N. PAPPAS
CHECKED BY: B. KIPP
SHEET 2 OF 78