VERMONT AGENCY OF TRANSPORTATION MONTPELIER, VERMONT

**Topsham BF 031-1(13)** **October 21, 2026**

## INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, November 13, 2026**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

**LOCATION:** LOCATED IN THE TOWN OF TOPSHAM ON VT ROUTE 25 OVER WAITS RIVER APPROXIMATELY 1.1 MILES SOUTH OF THE INTERSECTION WITH US ROUTE 302 AND EXTENDING NORTHERLY 0.028 MILES.

**TYPE OF CONSTRUCTION:** REPLACEMENT OF EXISTING BRIDGE WITH A NEW BURIED STRUCTURE ON ALIGNMENT INCLUDING NECESSARY APPROACH AND CHANNEL WORK.

**CONTRACT COMPLETION DATE:** This Contract shall be completed on or before **October 15, 2027.**

**BID BOND:** Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

**ENGINEER's ESTIMATE:** For this proposal the Engineer's Estimate is **Category E**.

**PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY:** On the VTrans website at:
https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting

**QUESTIONS:** During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30 PM on Wednesday, November 4, 2026.

**PREQUALIFICATION OF CONTRACTORS:** All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf, and must be submitted/uploaded through the iCXWeb website at: https://vtrans.exevision.com/icx/Index.aspx

**STANDARD SPECIFICATIONS:** The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications

**NON-COLLUSION AFFIDAVIT:** All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

**NONDISCRIMINATION IN AGENCY CONTRACTS:** VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

**MANDATORY ELECTRONIC BIDDING:** Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at: https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

**ESTIMATE OF QUANTITIES**

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|---|---|---|---|
| 199.8101 | INCENTIVE OR DISINCENTIVE (N.A.B.I.) | 156,400.000 | DL |
| 201.1000 | CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS | 1.000 | LS |
| 203.1500 | COMMON EXCAVATION | 1,100.000 | CY |
| 203.2700 | UNCLASSIFIED CHANNEL EXCAVATION | 1,000.000 | CY |
| 204.2200 | TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.) | 1.000 | CY |
| 204.2500 | STRUCTURE EXCAVATION | 1,300.000 | CY |
| 204.3000 | GRANULAR BACKFILL FOR STRUCTURES | 1,300.000 | CY |
| 210.1000 | COARSE-MILLING, BITUMINOUS PAVEMENT | 500.000 | SY |
| 225.0500 | RETAINING WALL, CONCRETE (WW1 - 712 SF) | 1.000 | LS |
| 225.0500 | RETAINING WALL, CONCRETE (WW2 - 257 SF) | 1.000 | LS |
| 225.0500 | RETAINING WALL, CONCRETE (WW3 - 200 SF) | 1.000 | LS |
| 225.0500 | RETAINING WALL, CONCRETE (WW4 - 783 SF) | 1.000 | LS |
| 301.3500 | SUBBASE OF DENSE GRADED CRUSHED STONE | 1,200.000 | CY |
| 401.1000 | AGGREGATE SURFACE COURSE | 60.000 | CY |
| 404.1100 | TACK COAT, EMULSIFIED ASPHALT | 20.000 | CWT |
| 406.0230 | BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III | 230.000 | TON |
| 406.0330 | BITUMINOUS CONCRETE PAVEMENT, TYPE IIIS, QA TIER III | 310.000 | TON |
| 406.3400 | BITUMINOUS CONCRETE PAVEMENT, NON-PAVER PLACED, TYPE IVS | 150.000 | SY |
| 406.9100 | PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.) | 1.000 | DL |
| 406.9200 | PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.) | 1.000 | DL |
| 501.3800 | PERFORMANCE-BASED CONCRETE, CLASS PCS | 45.000 | CY |
| 507.1100 | REINFORCING STEEL, LEVEL I | 3,900.000 | LB |
| 514.1000 | WATER REPELLENT, SILANE | 30.000 | GAL |
| 529.1500 | REMOVAL OF STRUCTURE ((1600 SF - EST) BRIDGE) | 1.000 | EACH |
| 540.1000 | PRECAST CONCRETE STRUCTURE (35FT X 13FT X 76FT RIGID FRAME) | 1.000 | LS |
| 543.1000 | CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE (MOMENT SLABS) | 19.000 | LS |
| 547.1000 | MICROPILE, CASED (10.75 INCH O.D.) | 1,776.000 | LF |
| 547.1500 | MICROPILE, UNCASED (9.25 INCH DIA) | 480.000 | LF |
| 547.2000 | MICROPILE OBSTRUCTION DRILLING AND REMOVAL | 100.000 | LF |
| 547.2500 | FURNISHING EQUIPMENT FOR INSTALLING MICROPILES | 1.000 | LS |
| 547.3000 | MICROPILE VERIFICATION LOAD TEST | 1.000 | EACH |
| 547.3500 | MICROPILE PROOF LOAD TEST | 2.000 | EACH |
| 601.9950 | CLEANING CULVERT PIPE, IN-PLACE (0 TO 24 INCHES, INCLUSIVE) | 120.000 | LF |
| 608.2501 | ALL-PURPOSE EXCAVATOR RENTAL, TYPE I | 10.000 | HR |
| 609.1000 | DUST CONTROL WITH WATER | 25.000 | MGAL |
| 613.0601 | E-STONE FILL, TYPE I | 20.000 | CY |
| 613.0603 | E-STONE FILL, TYPE III | 500.000 | CY |
| 613.1003 | STONE FILL, TYPE III | 460.000 | CY |
| 614.1000 | TEMPORARY RELOCATION OF STREAM | 1.000 | EACH |
| 621.0100 | REMOVAL OF GUARDRAIL | 610.000 | LF |
| 621.1060 | STEEL BEAM GUARDRAIL | 617.000 | LF |
| 621.1520 | ANCHOR FOR STEEL BEAM GUARDRAIL | 2.000 | EACH |
| 621.3030 | MTS, MGS, TANGENT, TL-3 | 1.000 | EACH |
| 630.1500 | FLAGGERS | 600.000 | HR |
| 631.1000 | FIELD OFFICE, ENGINEER'S | 1.000 | LS |

| | | | |
|---|---|---|---|
| 631.1600 | TESTING EQUIPMENT, CONCRETE | 1.000 | LS |
| 631.1700 | TESTING EQUIPMENT, BITUMINOUS | 1.000 | LS |
| 631.1900 | TESTING EQUIPMENT, GROUT | 1.000 | LS |
| 631.2600 | FIELD OFFICE COMMUNICATIONS (N.A.B.I.) | 3,000.000 | DL |
| 633.1000 | CPM SCHEDULE | 7.000 | EACH |
| 634.1000 | EMPLOYEE TRAINEESHIP | 520.000 | HR |
| 635.1100 | MOBILIZATION/DEMOBILIZATION | 1.000 | LS |
| 641.1100 | TRAFFIC CONTROL, ALL-INCLUSIVE | 1.000 | LS |
| 641.1500 | PORTABLE CHANGEABLE MESSAGE SIGN | 6.000 | EACH |
| 646.2010 | 4 INCH WHITE LINE, WATERBORNE PAINT | 900.000 | LF |
| 646.2111 | 4 INCH YELLOW LINE, WATERBORNE PAINT | 900.000 | LF |
| 649.1100 | GEOTEXTILE FOR ROADBED SEPARATOR | 1,800.000 | SY |
| 649.3100 | GEOTEXTILE UNDER STONE FILL | 900.000 | SY |
| 651.1500 | TURF ESTABLISHMENT, GENERAL SEED (VAOT NATURALIZED AREA TYPE II) | 1,150.000 | SY |
| 651.1600 | TURF ESTABLISHMENT, SPECIALTY SEED (VAOT POLLINATOR WET MIX) | 810.000 | SY |
| 651.3500 | TOPSOIL | 150.000 | CY |
| 651.4012 | GRUBBING MATERIAL, 12 INCH | 350.000 | SY |
| 653.0100 | EPSC PLAN | 1.000 | LS |
| 653.0200 | MONITORING EPSC PLAN | 50.000 | HR |
| 653.0300 | MAINTENANCE OF EPSC PLAN (N.A.B.I.) | 3,000.000 | DL |
| 653.1000 | HAY MULCH | 2.000 | TON |
| 653.2001 | ROLLED EROSION CONTROL PRODUCT, TYPE I | 1,400.000 | SY |
| 653.2501 | CHECK DAM, TYPE I | 5.000 | CY |
| 653.3400 | STABILIZED CONSTRUCTION ENTRANCE | 2.000 | EACH |
| 653.4500 | FILTER BAG | 1.000 | EACH |
| 653.4701 | SILT FENCE, TYPE I | 800.000 | LF |
| 653.5000 | BARRIER FENCE | 800.000 | LF |
| 653.5500 | PROJECT DEMARCATION FENCE | 200.000 | LF |
| 656.1200 | TUBELINGS | 72.000 | EACH |
| 656.6500 | LANDSCAPE WATERING | 6.000 | MGAL |
| 656.8000 | LANDSCAPE BACKFILL, TRUCK MEASUREMENT | 1.000 | CY |
| 675.2000 | TRAFFIC SIGN, FLAT SHEET ALUMINUM | 14.000 | SF |
| 675.3410 | SQUARE TUBE SIGN POST AND ANCHOR | 54.000 | LF |
| 675.5000 | SIGN REMOVAL, FLAT SHEET ALUMINUM | 7.000 | EACH |
| 676.1000 | DELINEATOR WITH STEEL POST | 3.000 | EACH |
| 690.0300 | PRICE ADJUSTMENT, ASPHALT (N.A.B.I.) | 1.000 | DL |

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.