VERMONT AGENCY OF TRANSPORTATION MONTPELIER, VERMONT

Chester ER P23-1(319) &
Chester ER P23-1(320)

November 18, 2026

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, December 11, 2026**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION:

Chester ER P23-1(319) - IN THE TOWN OF CHESTER ON VT ROUTE 103 APPROXIMATELY 1.513 MILES NORTH OF THE INTERSECTION WITH VT ROUTE 10.

Chester ER P23-1(320) - IN THE TOWN OF CHESTER ON VT ROUTE 103 APPROXIMATELY 1.397 MILES NORTH OF THE INTERSECTION WITH VT ROUTE 10.

TYPE OF CONSTRUCTION:

Chester ER P23-1(319) - REPLACEMENT OF BRIDGE 15 OVER UNNAMED TRIBUTARY WITH APPROACH ROADWAY AND RELATED CHANNEL WORK.

Chester ER P23-1(320) - REPLACEMENT OF CULVERT ON VT ROUTE 103 AT MM 9.038 OVER UNNAMED TRIBUTARY WITH APPROACH ROADWAY AND RELATED CHANNEL WORK.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **October 15, 2027.**

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER's ESTIMATE: For this proposal the Engineer's Estimate is **Category D**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30 PM on Wednesday, December 2, 2026.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf, and must be submitted/uploaded through the iCXWeb website at: https://vtrans.exevision.com/icx/Index.aspx

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any

contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at: https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (ER P23-1(319))	1.000	LS
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (ER P23-1(320))	1.000	LS
203.1500	COMMON EXCAVATION	1,725.000	CY
203.1600	SOLID ROCK EXCAVATION	173.000	CY
203.2700	UNCLASSIFIED CHANNEL EXCAVATION	396.000	CY
204.2000	TRENCH EXCAVATION OF EARTH	220.000	CY
204.2100	TRENCH EXCAVATION OF ROCK	11.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	2.000	CY
204.2500	STRUCTURE EXCAVATION	619.000	CY
204.3000	GRANULAR BACKFILL FOR STRUCTURES	560.000	CY
210.1000	COARSE-MILLING, BITUMINOUS PAVEMENT	510.000	SY
213.3015	MILLED RUMBLE STRIPS, SINUSOIDAL CENTERLINE	529.000	LF
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	1,260.000	CY
402.1300	AGGREGATE SHOULDERS, RAP	133.000	TON
404.1100	TACK COAT, EMULSIFIED ASPHALT	20.000	CWT
406.0230	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III	364.000	TON
406.0330	BITUMINOUS CONCRETE PAVEMENT, TYPE IIIS, QA TIER III	510.000	TON
406.3400	BITUMINOUS CONCRETE PAVEMENT, NON-PAVER PLACED, TYPE IVS	10.000	SY
406.9100	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	2.000	DL
406.9200	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	2.000	DL
514.1000	WATER REPELLENT, SILANE	15.000	GAL
540.1000	PRECAST CONCRETE STRUCTURE (8 FT X 7 FT X 62.53 FT BOX CULVERT, ER P23-1(319))	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (HEADWALLS, 9 FT X 16 FT, ER P23 -1(320))	1.000	LS
543.1500	CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE	1.000	EACH
601.2640	48 INCH CPEP(SL)	65.000	LF
601.9950	CLEANING CULVERT PIPE, IN-PLACE (0 TO 24 INCHES, INCLUSIVE)	22.000	LF
609.1000	DUST CONTROL WITH WATER	72.000	MGAL
613.0602	E-STONE FILL, TYPE II	224.000	CY
613.1001	STONE FILL, TYPE I	30.000	CY
613.1002	STONE FILL, TYPE II	111.000	CY
614.1000	TEMPORARY RELOCATION OF STREAM (ER P23-1(319))	1.000	EACH
614.1000	TEMPORARY RELOCATION OF STREAM (ER P23-1(320))	1.000	EACH
614.2000	IN-WATER SEDIMENT ISOLATION MEASURES (ER P23-1(319))	1.000	LS
614.2000	IN-WATER SEDIMENT ISOLATION MEASURES (ER P23-1(320))	1.000	LS
617.1100	REMOVE AND RESET MAILBOX, SINGLE SUPPORT	1.000	EACH
619.1700	YIELDING MARKER POSTS	4.000	EACH

621.0100	REMOVAL OF GUARDRAIL	675.000	LF
621.0200	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	1,740.000	LF
621.1060	STEEL BEAM GUARDRAIL	937.500	LF
621.1160	STEEL BEAM GUARDRAIL, NESTED	90.000	LF
621.1560	TRAFFIC BARRIER DELINEATOR	87.000	EACH
621.2400	TEMPORARY TRAFFIC BARRIER	1,740.000	LF
621.3030	MTS, MGS, TANGENT, TL-3	2.000	EACH
621.3130	MTS, MGS, FLARED, TL-3	6.000	EACH
621.7030	ENERGY ABSORPTION ATTENUATOR, TEMPORARY, TL-3	8.000	EACH
630.1000	UNIFORMED TRAFFIC OFFICERS	1,680.000	HR
630.1500	FLAGGERS	657.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1700	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.1900	TESTING EQUIPMENT, GROUT (ER P23-1(319))	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	3,000.000	DL
633.1000	CPM SCHEDULE (ER P23-1(319))	6.000	EACH
633.1000	CPM SCHEDULE (ER P23-1(320))	6.000	EACH
635.1100	MOBILIZATION/DEMOBILIZATION (ER P23-1(319))	1.000	LS
635.1100	MOBILIZATION/DEMOBILIZATION (ER P23-1(320))	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE (ER P23-1(319))	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE (ER P23-1(320))	1.000	LS
641.1500	PORTABLE CHANGEABLE MESSAGE SIGN	4.000	EACH
641.2200	TEMPORARY TRAFFIC CONTROL SIGNAL SYSTEM, PORTABLE	2.000	EACH
646.4040	DURABLE 4 INCH WHITE LINE, POLYUREA	1,060.000	LF
646.4140	DURABLE 4 INCH YELLOW LINE, POLYUREA	660.000	LF
646.6000	TEMPORARY 4 INCH WHITE LINE	2,120.000	LF
646.6012	TEMPORARY 4 INCH WHITE LINE, TYPE C TAPE	4,450.000	LF
646.6100	TEMPORARY 4 INCH YELLOW LINE	1,320.000	LF
646.6812	TEMPORARY 24 INCH STOP BAR, TYPE C TAPE	105.000	LF
646.7600	LINE STRIPING TARGETS	204.000	EACH
646.8600	PAVEMENT MARKING MASK	1,845.000	SF
649.3100	GEOTEXTILE UNDER STONE FILL	248.000	SY
651.1500	TURF ESTABLISHMENT, GENERAL SEED	1,525.000	SY
651.3500	TOPSOIL	167.000	CY
651.4012	GRUBBING MATERIAL, 12 INCH	252.000	SY
653.0100	EPSC PLAN (ER P23-1(319))	1.000	LS
653.0100	EPSC PLAN (ER P23-1(320))	1.000	LS
653.0200	MONITORING EPSC PLAN	80.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	8,000.000	DL
653.1000	HAY MULCH	0.700	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	615.000	SY
653.2501	CHECK DAM, TYPE I	50.000	CY
653.3400	STABILIZED CONSTRUCTION ENTRANCE	4.000	EACH
653.4702	SILT FENCE, TYPE II	346.000	LF
653.5000	BARRIER FENCE	1,380.000	LF
653.5500	PROJECT DEMARCATION FENCE	372.000	LF
675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	1.000	SF
675.3410	SQUARE TUBE SIGN POST AND ANCHOR	20.000	LF
675.5000	SIGN REMOVAL, FLAT SHEET ALUMINUM	2.000	EACH
676.1000	DELINEATOR WITH STEEL POST	8.000	EACH
676.1200	REMOVAL OF EXISTING DELINEATOR AND POST	6.000	EACH
690.0300	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	2.000	DL

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.