VERMONT AGENCY OF TRANSPORTATION MONTPELIER, VERMONT

Killington-Stockbridge ER STP 022-1(25) **November 04, 2026**

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, December 11, 2026**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION: BEGINNING AT THE INTERSECTION OF VT ROUTE 100 AND US ROUTE 4 IN THE TOWN OF KILLINGTON, AT MILE MARKER 0.021 = STATION 1+09.00 AND EXTENDING NORTHERLY ALONG VT ROUTE 100 FOR A DISTANCE OF APPROXIMATELY 56956.13 FT (10.787 MILES) TO AN ENDING POINT AT MILE MARKER 1.922 = STATION B 101+50.00 NEAR THE INTERSECTION OF ROUTE 100 AND VT ROUTE 107 IN THE TOWN OF STOCKBRIDGE.

TYPE OF CONSTRUCTION: WORK TO BE PERFORMED UNDER THIS PROJECT INCLUDES COARSE-MILLING, COLD IN-PLACE RECYCLING, RESURFACING WITH LEVELING AND WEARING COURSES, NEW PAVEMENT MARKINGS, SIGNAGE, GUARDRAIL IMPROVEMENTS, REPLACEMENT OF CULVERTS, DRAINAGE IMPROVEMENTS AND OTHER RELATED HIGHWAY ITEMS.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **October 13, 2028.**

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER's ESTIMATE: For this proposal the Engineer's Estimate is **Category G**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30 PM on Wednesday, November 18, 2026.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf, and must be submitted/uploaded through the iCXWeb website at: https://vtrans.exevision.com/icx/Index.aspx

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at: https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
199.8121	LIQUIDATED DAMAGES, INTERIM COMPLETION DATE (N.A.B.I.)	1.000	DL
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	1.000	LS
203.1500	COMMON EXCAVATION	2,130.000	CY
203.1700	UNCLASSIFIED EXCAVATION	100.000	CY
203.2700	UNCLASSIFIED CHANNEL EXCAVATION	220.000	CY
203.3000	EARTH BORROW	2,200.000	CY
204.2000	TRENCH EXCAVATION OF EARTH	7,750.000	CY
204.2100	TRENCH EXCAVATION OF ROCK	2,600.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000	CY
204.2500	STRUCTURE EXCAVATION	450.000	CY
204.3000	GRANULAR BACKFILL FOR STRUCTURES	1,480.000	CY
210.1000	COARSE-MILLING, BITUMINOUS PAVEMENT	181,100.000	SY
213.3015	MILLED RUMBLE STRIPS, SINUSOIDAL CENTERLINE	29,050.000	LF
240.0100001	TEMPORARY COVER PAVEMENT	3,590.000	TON
240.0100002	TEMPORARY ROADWAY WIDENING (MM 0.318)	1.000	LS
240.0100002	TEMPORARY ROADWAY WIDENING (MM 3.193)	1.000	LS
301.2800	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	9,480.000	TON
301.4000001	BASE OF RAP	2,470.000	TON
402.1300	AGGREGATE SHOULDERS, RAP	9,000.000	TON
404.1100	TACK COAT, EMULSIFIED ASPHALT	2,000.000	CWT
404.3100	FOG SEAL, EMULSIFIED ASPHALT	2,675.000	CWT
406.0310	BITUMINOUS CONCRETE PAVEMENT, TYPE IIIS, QA TIER I	21,060.000	TON
406.0410	BITUMINOUS CONCRETE PAVEMENT, TYPE IVS, QA TIER I	5,810.000	TON
406.2400	BITUMINOUS CONCRETE PAVEMENT, SURFACE PREPARATION, TYPE IVS	1.000	TON
406.3400	BITUMINOUS CONCRETE PAVEMENT, NON-PAVER PLACED, TYPE IVS	4,000.000	SY
406.9100	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	1.000	DL
406.9200	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	1.000	DL
406.9300	PAY ADJUSTMENT, BCP, LONGITUDINAL JOINT DENSITY (N.A.B.I.)	1.000	DL
406.9400	PAY ADJUSTMENT, BCP, PAVEMENT ROUGHNESS (N.A.B.I.)	1.000	DL
410.1000	MATERIAL TRANSFER VEHICLE	26,870.000	TON
414.0400	COLD IN-PLACE RECYCLING, 4 INCH DEPTH	184,200.000	SY
414.5100	AGGREGATE FOR CIR	6,010.000	TON
414.5200	PORTLAND CEMENT FOR CIR	410.000	TON
507.1100	REINFORCING STEEL, LEVEL I	365.000	LB
507.1600	DRILLING AND GROUTING DOWELS	15.000	LF
514.1000	WATER REPELLENT, SILANE	23.000	GAL
525.3120	BRIDGE RAILING, GALVANIZED 2 RAIL BOX BEAM	50.000	LF
529.1500	REMOVAL OF STRUCTURE (4 FT X 4 FT CONCRETE BOX CULVERT)	2.000	EACH
529.2000	PARTIAL REMOVAL OF STRUCTURE (4 FT X 4FT X 2 FT CONCRETE BOX)	1.000	EACH

540.1000	PRECAST CONCRETE STRUCTURE (10 FT X 5 FT X 38 FT BOX AND WINGWALLS)	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (4 FT X 4 FT X 11 FT BOX EXT AND WW END SECTION)	1.000	LS
540.1000	PRECAST CONCRETE STRUCTURE (8 FT X 6 FT X 34-8 FT BOX AND WINGWALLS)	1.000	LS
540.1500	PRECAST CONCRETE STRUCTURE (18 INCH HEADWALL)	12.000	EACH
540.1500	PRECAST CONCRETE STRUCTURE (24 INCH HEADWALL)	8.000	EACH
540.1500	PRECAST CONCRETE STRUCTURE (30 INCH HEADWALL)	7.000	EACH
540.1500	PRECAST CONCRETE STRUCTURE (36 INCH HEADWALL)	2.000	EACH
540.1500	PRECAST CONCRETE STRUCTURE (42 INCH HEADWALL)	2.000	EACH
541.2200	CONCRETE, CLASS B	5.000	CY
580.1101	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS I	2.000	SY
580.1102	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS II	2.000	SY
580.1103	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS III	1.000	CY
601.0850	42 INCH RCP CLASS III	50.000	LF
601.2610	15 INCH CPEP(SL)	130.000	LF
601.2615	18 INCH CPEP(SL)	940.000	LF
601.2620	24 INCH CPEP(SL)	450.000	LF
601.2625	30 INCH CPEP(SL)	350.000	LF
601.2630	36 INCH CPEP(SL)	100.000	LF
601.7010	15 INCH CPEPES	3.000	EACH
601.7015	18 INCH CPEPES	21.000	EACH
601.7020	24 INCH CPEPES	10.000	EACH
601.7025	30 INCH CPEPES	8.000	EACH
601.7030	36 INCH CPEPES	2.000	EACH
601.9950	CLEANING CULVERT PIPE, IN-PLACE (0 TO 24 INCHES, INCLUSIVE)	1,400.000	LF
601.9960	CLEANING CULVERT PIPE, IN-PLACE (GREATER THAN 24 INCHES)	220.000	LF
602.4500	CORING CONCRETE	16.000	EACH
604.1800	PRECAST REINFORCED CONCRETE DI WITH CAST IRON GRATE	4.000	EACH
604.4000	CHANGING ELEVATION OF DIS, CATCH BASINS, OR MANHOLES	10.000	EACH
604.4101	REHABILITATING DIS, CATCH BASINS, OR MANHOLES, CLASS I	11.000	EACH
604.4102	REHABILITATING DIS, CATCH BASINS, OR MANHOLES, CLASS II	1.000	EACH
604.4103	REHABILITATING DIS, CATCH BASINS, OR MANHOLES, CLASS III	1.000	EACH
605.1006	UNDERDRAIN PIPE, 6 INCH	26,950.000	LF
608.1001	BULLDOZER RENTAL, TYPE I	20.000	HR
608.1500	POWER GRADER RENTAL	80.000	HR
608.2501	ALL-PURPOSE EXCAVATOR RENTAL, TYPE I	370.000	HR
608.2601	SPECIAL PURPOSE EXCAVATOR RENTAL, TYPE I	600.000	HR
608.3001	POWER BROOM RENTAL, TYPE I	440.000	HR
608.3002	POWER BROOM RENTAL, TYPE II	60.000	HR
608.3700	TRUCK RENTAL	1,620.000	HR
608.4001	LOADER RENTAL, TYPE I	50.000	HR
609.1500	DUST CONTROL WITH CALCIUM CHLORIDE	3.000	TON
613.0601	E-STONE FILL, TYPE I	120.000	CY
613.0604	E-STONE FILL, TYPE IV	20.000	CY
613.1001	STONE FILL, TYPE I	3,136.000	CY
613.1002	STONE FILL, TYPE II	705.000	CY
613.1004	STONE FILL, TYPE IV	50.000	CY
614.1000	TEMPORARY RELOCATION OF STREAM (MM 0.318)	1.000	EACH
614.1000	TEMPORARY RELOCATION OF STREAM (MM 1.777)	1.000	EACH
614.1000	TEMPORARY RELOCATION OF STREAM (MM 3.193)	1.000	EACH
616.2000	GRANITE SLOPE EDGING	50.000	LF
616.2702	CAST-IN-PLACE CONCRETE CURB, TYPE B	320.000	LF
616.3101	BITUMINOUS CONCRETE CURB, TYPE A	170.000	LF
616.4700	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	8.000	TON
617.1100	REMOVE AND RESET MAILBOX, SINGLE SUPPORT	48.000	EACH

617.1200	REMOVE AND RESET MAILBOX, MULTIPLE SUPPORT	1.000	EACH
619.1700	YIELDING MARKER POSTS	355.000	EACH
620.5000	REMOVING AND RESETTING FENCE	110.000	LF
621.0100	REMOVAL OF GUARDRAIL	14,150.000	LF
621.0200	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	960.000	LF
621.0210	REMOVE AND RESET GUARDRAIL	1,000.000	LF
621.0220	ADJUST HEIGHT OF GUARDRAIL	175.000	LF
621.0300	REPLACE GUARDRAIL BEAM UNIT, W-BEAM	14.000	EACH
621.1080	STEEL BEAM GUARDRAIL WITH 8 FOOT POSTS	24,262.500	LF
621.1180	STEEL BEAM GUARDRAIL WITH 8 FOOT POSTS, NESTED	400.000	LF
621.1520	ANCHOR FOR STEEL BEAM GUARDRAIL	93.000	EACH
621.2400	TEMPORARY TRAFFIC BARRIER	6,960.000	LF
621.7030	ENERGY ABSORPTION ATTENUATOR, TEMPORARY, TL-3	4.000	EACH
621.8120	GUARDRAIL APPROACH SECTION, 2 RAIL BOX BEAM	8.000	EACH
630.1000	UNIFORMED TRAFFIC OFFICERS	6,000.000	HR
630.1500	FLAGGERS	22,700.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1600	TESTING EQUIPMENT, CONCRETE	1.000	LS
631.1700	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	6,000.000	DL
633.1000	CPM SCHEDULE	20.000	EACH
634.1000	EMPLOYEE TRAINEESHIP	1,040.000	HR
635.1100	MOBILIZATION/DEMOBILIZATION	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE (MM 0.318)	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE (MM 3.193)	1.000	LS
641.1500	PORTABLE CHANGEABLE MESSAGE SIGN	4.000	EACH
641.2200	TEMPORARY TRAFFIC CONTROL SIGNAL SYSTEM, PORTABLE	2.000	EACH
646.6020	TEMPORARY 4 INCH WHITE LINE, PAINT	113,750.000	LF
646.6120	TEMPORARY 4 INCH YELLOW LINE, PAINT	102,200.000	LF
646.6420	TEMPORARY 8 INCH WHITE LINE, PAINT	110.000	LF
646.6520	TEMPORARY 8 INCH YELLOW LINE, PAINT	460.000	LF
646.6820	TEMPORARY 24 INCH STOP BAR, PAINT	530.000	LF
646.6920	TEMPORARY LETTER OR SYMBOL, PAINT	141.000	EACH
646.7600	LINE STRIPING TARGETS	28,400.000	EACH
649.1100	GEOTEXTILE FOR ROADBED SEPARATOR	10,665.000	SY
649.3100	GEOTEXTILE UNDER STONE FILL	3,815.000	SY
651.1500	TURF ESTABLISHMENT, GENERAL SEED	42,690.000	SY
651.3500	TOPSOIL	4,850.000	CY
651.4006	GRUBBING MATERIAL, 6 INCH	3,430.000	SY
651.4012	GRUBBING MATERIAL, 12 INCH	400.000	SY
653.0100	EPSC PLAN	1.000	LS
653.0200	MONITORING EPSC PLAN	60.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	5,000.000	DL
653.1000	HAY MULCH	20.000	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	11,580.000	SY
653.2501	CHECK DAM, TYPE I	220.000	CY
653.4001	INLET PROTECTION DEVICE, TYPE I	30.000	EACH
653.4002	INLET PROTECTION DEVICE, TYPE II	5.000	EACH
653.4003	INLET PROTECTION DEVICE, TYPE III	920.000	CY
653.4500	FILTER BAG	6.000	EACH
653.4701	SILT FENCE, TYPE I	15,330.000	LF
653.4702	SILT FENCE, TYPE II	9,990.000	LF
653.5000	BARRIER FENCE	23,370.000	LF
653.5500	PROJECT DEMARCATION FENCE	27,390.000	LF
653.6000	EROSION LOG	5,880.000	LF

675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	1,170.000	SF
675.3410	SQUARE TUBE SIGN POST AND ANCHOR	3,530.000	LF
675.5000	SIGN REMOVAL, FLAT SHEET ALUMINUM	276.000	EACH
675.6000	RESETTING SIGNS	14.000	EACH
675.6000001	REMOVE AND RESET PRIVATE SIGN ASSEMBLY, NON-LIGHTED	1.000	EACH
676.1000	DELINEATOR WITH STEEL POST	185.000	EACH
676.1200	REMOVAL OF EXISTING DELINEATOR AND POST	9.000	EACH
676.1500	REMOVE AND REPLACE DELINEATOR	22.000	EACH
681.1510	REMOVE AND RESET ANCILLARY ITEM (BOULDERS)	9.000	EACH
690.0300	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	1.000	DL
690.0400	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	1.000	DL
OPTION - PAVEMENT MARKINGS - EPOXY PAVEMENT MARKING ITEMS			
646.4030	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	113,750.000	LF
646.4130	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	102,200.000	LF
646.4430	DURABLE 8 INCH WHITE LINE, EPOXY PAINT	110.000	LF
646.4530	DURABLE 8 INCH YELLOW LINE, EPOXY PAINT	460.000	LF
646.4830	DURABLE 24 INCH STOP BAR, EPOXY PAINT	530.000	LF
646.4930	DURABLE LETTER OR SYMBOL, EPOXY PAINT	141.000	EACH
OPTION - PAVEMENT MARKINGS - POLYUREA PAVEMENT MARKING ITEMS			
646.4040	DURABLE 4 INCH WHITE LINE, POLYUREA	113,750.000	LF
646.4140	DURABLE 4 INCH YELLOW LINE, POLYUREA	102,200.000	LF
646.4440	DURABLE 8 INCH WHITE LINE, POLYUREA	110.000	LF
646.4540	DURABLE 8 INCH YELLOW LINE, POLYUREA	460.000	LF
646.4840	DURABLE 24 INCH STOP BAR, POLYUREA	530.000	LF
646.4940	DURABLE LETTER OR SYMBOL, POLYUREA	141.000	EACH
ALTERNATE - COLD-IN-PLACE RECYCLING - EMULSIFIED ASPHALT FOR CIR			
414.5300	EMULSIFIED ASPHALT FOR CIR	32,100.000	CWT
ALTERNATE - COLD-IN-PLACE RECYCLING - FOAMED ASPHALT FOR CIR			
414.5400	FOAMED ASPHALT FOR CIR	20,100.000	CWT

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.