VERMONT AGENCY OF TRANSPORTATION MONTPELIER, VERMONT

Charleston STP CULV(113) **November 25, 2026**

INVITATION FOR BIDS

Submitted bids will be opened electronically at 11:00 AM on **Friday, December 18, 2026**; and will be posted to the Vermont Agency of Transportation website. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

LOCATION: BEGINNING IN THE TOWN OF CHARLESTON 14,611.76 FT SOUTH OF THE INTERSECTION BETWEEN VT 105 AND VT 5A AT STA 56+50.00 (MM 1.070) EXTENDING NORTHEASTERLY APPROXIMATELY 130.00 FT TO STA 57+80.00 (MM 1.095)

TYPE OF CONSTRUCTION: WORK TO BE PERFORMED UNDER THIS PROJECT INCLUDES REPLACEMENT OF AN EXISTING METAL CULVERT WITH A NEW PRECAST CONCRETE BOX STRUCTURE AND RELATED HIGHWAY ITEMS.

CONTRACT COMPLETION DATE: This Contract shall be completed on or before **October 15, 2027.**

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER's ESTIMATE: For this proposal the Engineer's Estimate is **Category D**.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: On the VTrans website at:
https://vtrans.vermont.gov/contract-admin/bids-requests/construction-contracting

QUESTIONS: During the advertisement period, all questions shall be addressed solely to the Office of Contract Administration via email: AOT.ConstructionContractingInquiry@vermont.gov. All inquiries must be received by 4:30 PM on Wednesday, December 9, 2026.

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold **both** current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: https://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf, and must be submitted/uploaded through the iCXWeb website at: https://vtrans.exevision.com/icx/Index.aspx

STANDARD SPECIFICATIONS: The work to be performed under this Contract shall be in accordance with the 2024 Standard Specifications for Construction, as modified. The Standard Specifications are available on the Vermont Agency of Transportation website.
https://vtrans.vermont.gov/highway/construct-material/construct-services/pre-contractspecifications

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only electronic bids will be accepted by the Agency. For information on electronic bidding with the Agency, please visit our website at: https://vtrans.vermont.gov/contract-admin/resources/construction-contracting/electronic-bidding

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

ESTIMATE OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
201.1000	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	1.000	LS
203.1500	COMMON EXCAVATION	1,150.000	CY
203.2700	UNCLASSIFIED CHANNEL EXCAVATION	200.000	CY
203.3100	SAND BORROW	650.000	CY
204.2200	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000	CY
204.2500	STRUCTURE EXCAVATION	875.000	CY
204.3000	GRANULAR BACKFILL FOR STRUCTURES	425.000	CY
210.1000	COARSE-MILLING, BITUMINOUS PAVEMENT	625.000	SY
240.0100003	TEMPORARY TRAFFIC DIVERSION	1.000	LS
301.3500	SUBBASE OF DENSE GRADED CRUSHED STONE	550.000	CY
402.1300	AGGREGATE SHOULDERS, RAP	30.000	TON
404.1100	TACK COAT, EMULSIFIED ASPHALT	7.000	CWT
406.0230	BITUMINOUS CONCRETE PAVEMENT, TYPE IIS, QA TIER III	140.000	TON
406.0330	BITUMINOUS CONCRETE PAVEMENT, TYPE IIIS, QA TIER III	150.000	TON
406.3400	BITUMINOUS CONCRETE PAVEMENT, NON-PAVER PLACED, TYPE IVS	10.000	SY
406.9100	PAY ADJUSTMENT, BCP, MIXTURE PROPERTIES (N.A.B.I.)	1.000	DL
406.9200	PAY ADJUSTMENT, BCP, MAT DENSITY (N.A.B.I.)	1.000	DL
514.1000	WATER REPELLENT, SILANE	4.000	GAL
540.1000	PRECAST CONCRETE STRUCTURE (6 FT X 8 FT X 119 FT BOX CULVERT)	1.000	LS
608.2501	ALL-PURPOSE EXCAVATOR RENTAL, TYPE I	40.000	HR
608.3700	TRUCK RENTAL	40.000	HR
613.0602	E-STONE FILL, TYPE II	170.000	CY
614.1000	TEMPORARY RELOCATION OF STREAM	1.000	EACH
630.1000	UNIFORMED TRAFFIC OFFICERS	100.000	HR
630.1500	FLAGGERS	1,000.000	HR
631.1000	FIELD OFFICE, ENGINEER'S	1.000	LS
631.1700	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.2600	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	3,000.000	DL
633.1000	CPM SCHEDULE	3.000	EACH
635.1100	MOBILIZATION/DEMOBILIZATION	1.000	LS
641.1100	TRAFFIC CONTROL, ALL-INCLUSIVE	1.000	LS
641.1500	PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH
641.2200	TEMPORARY TRAFFIC CONTROL SIGNAL SYSTEM, PORTABLE	1.000	EACH
646.2010	4 INCH WHITE LINE, WATERBORNE PAINT	950.000	LF
646.2111	4 INCH YELLOW LINE, WATERBORNE PAINT	950.000	LF
649.1100	GEOTEXTILE FOR ROADBED SEPARATOR	975.000	SY
651.1500	TURF ESTABLISHMENT, GENERAL SEED	1,640.000	SY
651.1600	TURF ESTABLISHMENT, SPECIALTY SEED (WET AREA SEED MIX)	760.000	SY
651.3500	TOPSOIL	275.000	CY
651.4006	GRUBBING MATERIAL, 6 INCH	100.000	SY
653.0100	EPSC PLAN	1.000	LS
653.0200	MONITORING EPSC PLAN	20.000	HR
653.0300	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	4,000.000	DL
653.1200	STRAW MULCH	1.000	TON
653.2001	ROLLED EROSION CONTROL PRODUCT, TYPE I	2,400.000	SY
653.3400	STABILIZED CONSTRUCTION ENTRANCE	2.000	EACH

653.4500	FILTER BAG	1.000	EACH
653.4701	SILT FENCE, TYPE I	600.000	LF
653.5000	BARRIER FENCE	850.000	LF
653.6000	EROSION LOG	1,200.000	LF
675.2000	TRAFFIC SIGN, FLAT SHEET ALUMINUM	1.000	SF
675.3410	SQUARE TUBE SIGN POST AND ANCHOR	12.000	LF
675.5000	SIGN REMOVAL, FLAT SHEET ALUMINUM	2.000	EACH
676.1000	DELINEATOR WITH STEEL POST	2.000	EACH
690.0300	PRICE ADJUSTMENT, ASPHALT (N.A.B.I.)	1.000	DL

The estimates of quantities are not guaranteed, but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality, and any and all technicalities in bids, and to accept such bids as may be deemed in the best interest of the awarding agency.